

7th Framework Programme INFSO-ICT 285285

V2G Conformance Test Specifications

Deliverable n.	6.1	V2G Conform	nance Test Spe	ecifications
Workpackage	6 Conformance and Interoperability Testing			rability Testing
Editors	Miguel Ángel Reina Ortega (ETSI)			
Authors	Miguel Ángel Reina Ortega (ETSI) Antonio Plaza Ortega (ETSI) Zoltán Jakó (BroadBit)			
Status	Final			
Distribution	Public (PU)			
Issue date	2013-02-12 Creation date 2012-10-05			
European Commission Information Society and Media	Project co-funded by the European Commission DG-Information Society and Media in the 7th Framework Programme		SEVENTH FRAMEWORK PROGRAMME	

TABLE OF CONTENTS

LIST OF ABBREVIATIONS	6
LIST OF FIGURES	7
LIST OF TABLES	8
REVISION CHART AND HISTORY LOG	9
EXECUTIVE SUMMARY	10
1. INTRODUCTION	11
2. METHODOLOGY	12
2.1. CONFORMANCE TESTING	12
2.2. POWERUP IMPLEMENTATIONS UNDER TEST	13
2.3. ETSI TESTING METHODOLOGY	14
3. V2G TEST SPECIFICATIONS	16
3.1. PROTOCOL IMPLEMENTATION STATEMENT CONFORMANCE (PICS)	16
3.2. TEST SUITE STRUCTURE AND TEST PURPOSES (TSS&TP)	18
3.2.1 Test Suite Structure	19
3.2.2 Test Configurations	20
3.2.3 Test Purpose Identifier Naming Convention	21
3.2.4 Test Purpose Template	23
3.3. ABSTRACT TEST SUITE (ATS)	25
3.3.1 Point of Control and Observation	26
3.3.2 V2G Abstract Protocol Tester	27
3.3.3 V2G General Test Architecture	28
3.3.4 V2G Test Architecture Design	29
3.3.5 Ports and Primitives	31
3.3.6 TTCN-3 Test Cases	33
4. V2G CONFORMANCE TEST PLATFORM	36
	Page 2 of 172

4.1 Con	ISTRAINTS	36
4.2 HAF	RDWARE AND TEST TOOL	37
4.3 CODECS		38
4.3.1	Advanced details	38
4.4.1	Lower Tester	40
4.4.2	Platform Adapter	41
4.4.3	Upper Tester	41
5. CONCLUSION	ONS	42
REFERENCES		43
ANNEX A: PR	OTOCOL IMPLEMENTATION CONFORMANCE STATEMENTS (PICS)	44
A.1 V2G EN	TITY ROLE	44
A.2 CHARGII	NG MODE	44
A.3 IDENTIFI	CATION MODE	44
A.4 OPTION	AL SETS	44
А.5 Ркотос	OL STACK	45
A.6 SECC D	ISCOVERY PROTOCOL (SDP)	45
A.7 V2G AP	PLICATION LAYER PROTOCOL HANDSHAKE	46
A.8 V2G AP	PLICATION LAYER MESSAGES	46
ANNEX B: TE	ST PURPOSES FOR EVCC	47
B.1 SECC DI	SCOVERY	48
B.2 APPLICA	TION LAYER MESSAGES	51
B.2.1. H	andshake Protocol	51
B.2.2 Se.	ssion Setup	53
B.2.3 Se	rvice Discovery	55
B.2.4 Se	rvice Details	58
B.2.5 Se	rvice and Payment Selection	62
		Page 3 of 172

B.2.6 Certificate Update	69
B.2.7 Certificate Installation	72
B.2.8 Payment Details	
B.2.9 Contract Authentication	
B.2.10 Charge parameter Discovery	84
B.2.11 Power Delivery	89
B.2.12 Session Stop	96
B.2.13 Charging status	98
B.2.14 Metering Receipt	101
B.2.15 Cable Check	
B.2.16 Pre Charge	106
B.2.17 Current Demand	
B.2.18 Welding Detection	112
ANNEX C: TEST PURPOSES FOR SECC	114
C.1 SECC DISCOVERY	114
C.2 APPLICATION LAYER MESSAGES	118
C.2.1. Handshake Protocol	118
C.2.2 Session Setup	121
C.2.3 Service Discovery	
C.2.4 Service Details	124
C.2.5 Service and Payment Selection	
C.2.6 Certificate Update	128
C.2.7 Certificate Installation	133
C.2.8 Payment Details	136
C.2.9 Contract Authentication	138
C.2.10 Charge parameter Discovery	140

Page 4 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 28528!

C.2.11 Power Delivery	144
C.2.12 Session Stop	152
C.2.13 Charging status	154
C.2.14 Metering Receipt	156
C.2.15 Cable Check	158
C.2.16 Pre Charge	160
C.2.17 Current Demand	162
C.2.18 Welding Detection	164
ANNEX D: ATS CONVENTIONS	166
ANNEX E: V2G PROTOCOL EXCHANGE	168
E.1 OVERVIEW OF AC V2G PROTOCOL MESSAGE EXCHANGE	168
E.2 OVERVIEW OF DC V2G PROTOCOL MESSAGE EXCHANGE	169
ANNEX F: WHAT IS TTCN-3?	170
F.1 TTCN-3 IS EASY TO LEARN	170
F.2 TTCN-3 IS INTERNATIONALLY STANDARDIZED	171
F.3 THE TTCN-3 APPROACH TO TESTING IS EXTREMELY FLEXIBLE	171
F 4 TTCN-3 CAN BE LISED IN MANY TYPES OF TESTING	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

LIST OF ABBREVIATIONS

ABBREVIATION	DESCRIPTION
ATS	Abstract Test Suite
ETSI	European Telecommunication Standard Institute
EVCC	Electric Vehicle Communication Controller
ISO	International Organization for Standardization
IUT	Implementation Under Test
PICS	Protocol Implementation Conformance Statement
SDP	SECC Discovery Protocol
SECC	Supply Equipment Communication Controller
SUT	System Under Test
ТСР	Transmission Control Protocol
TP	Test Purpose
TSS	Test Suite Structure
TTCN-3	Testing and Test Control Notation version 3
UDP	User Datagram Protocol
V2G	Vehicle to Grid
V2GTP	V2G Transfer Protocol
WP	Work Package

PowerUp Final V2G Architecture	Public	Copyright PowerUp
-		Contract N. 285285

LIST OF FIGURES

Figure 1. PowerUp System Architecture11
Figure 2. General Conformance Testing Architecture
Figure 3. Detailed General Conformance Testing Architecture
Figure 4. Conformance Test Methodology
Figure 5. Elements for PICS development
Figure 6. Generic Test Suite Structure18
Figure 7. Elements for TSS&TP development
Figure 8. Test configuration 120
Figure 9. Test configuration 221
Figure 10. Test configuration 321
Figure 11. Elements for ATS development26
Figure 12. PCOs' location
Figure 13. Abstract Protocol Tester for V2G Application Layer protocol
Figure 14. Abstract Protocol Tester for Session Discovery protocol
Figure 15. High level V2G Test Architecture
Figure 16. V2G Test Architecture
Figure 17. Test case architecture
Figure 18. Relationship between CODECS java classes

PowerUp Final V2G Architecture	Public	Copyright PowerUp
-		Contract N. 285285

LIST OF TABLES

Table 1. Test Suite Structure	19
Table 2. Test Purpose Identifiers	21
Table 3. Test Purpose Template	23
Table 4. Test Purpose - Example 1	24
Table 5. Test Purpose - Example 2	25
Table 6. Points of Control and Observation	26
Table 7 FTSI generic TTCN-3 naming conventions	166

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

REVISION CHART AND HISTORY LOG

REV	DATE	REASON
0.1	2012-10-05	First draft
0.2	2012-10-16	Second draft
0.3	2012-11-20	Third draft
0.4	2012-12-10	Fourth draft
0.5	2012-12-19	Core document - Final draft
0.6	2012-12-21	Annexes – Final Draft
0.7	2012-02-01	Update from peer review

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

EXECUTIVE SUMMARY

Users' needs are changing rapidly, generating new challenges and leading to systems that are increasingly complex. This complexity compromises interoperability but, from a consumers point of view, interoperability becomes a must.

With the desire to achieve this interoperability, standardization is crucial in a multi-vendor, multi-network and multi-service environment. Once standards are defined prototypes and products can be developed, but the interpretation of these standards can vary, and different products from different manufacturers are sometimes not able to work together. Testing is an essential tool to mitigate this problem; first defining a robust test methodology, then creating a complete set of test specifications, and finally developing test tools to test against those specifications.

PowerUp aims to develop the Vehicle-To-Grid (V2G) interface for Electric Vehicle charging, involving a full development cycle of physical/link-layer specification, charging control protocol design, prototyping, conformance testing, field trials, and standardization. WP6, and more specifically task 6.1, aims to develop a complete set of conformance test specifications for the V2G interface. These conformance test specifications rely on the V2G base specifications from the standard ISO/IEC 15118-2 [1] augmented with those developed in PowerUp WP4.

This deliverable includes a complete set of conformance test specifications for the V2G interface; Protocol Implementation Conformance Statements (PICS), Test Suite Structure and Test Purposes (TSS&TP) and Abstract Test Suite (ATS) by following the ISO 9646 testing methodology and ETSI recommendations.

The deliverable is arranged in 5 chapters:

- Chapter 1 gives an introduction to Conformance testing
- Chapter 2 provides an overview of the conformance testing methodology used for these test specifications
- Chapter 3 presents the different parts of the V2G test specifications
- Chapter 4 gives detailed information about the V2G test platform implementation
- Finally, Chapter 5 concludes the deliverable.

Page 10 of 172	
----------------	--

Copyright	PowerUp
Contract N	. 285285

1. INTRODUCTION

Testing is one of the most important activities during the development of a system, and diverse techniques exist to completely cover all the functionality specified and developed in specific systems. The more complex the system, the more complex the testing techniques that are needed.

The PowerUp project has defined a complex, heterogeneous, system shown in Figure 1 below, and described in other PowerUp deliverables ([2], [5], [7]). Therefore, the range of testing techniques that can be applied to this vehicular environment is very high.




Figure 1. PowerUp System Architecture

From a testing perspective, this architecture demands a range of testing techniques covering software, performance, integration, robustness etc. PowerUp covers some of these approaches in other Work Packages (WP7 covers integration testing, and WP5 covers software testing, for example).

WP6 deals with conformance and interoperability testing for **the V2G standard** interface between the A-VG2 and the I-V2G based on ISO 15118-2 [1].

This deliverable addresses the development of the conformance test specification following the methodology described in section 2. Interoperability testing is covered by the PowerUp D6.2 [3].

Page 11 of 172	
----------------	--

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

2. METHODOLOGY

2.1. Conformance testing

Conformance testing checks a specific (part of a) product for compliance to requirements in a Base Standard. This technique is mainly applied in protocol testing, and PowerUp has used it in WP6.

Figure 2 illustrates the generic view of a conformance testing architecture, and Figure 3 shows a real example of a typical test system.



Figure 2. General Conformance Testing Architecture

This architecture is divided into two basic components; the Implementation Under Test (IUT) is the specific product to be tested, and the Test System executes the tests (i.e. executing test scripts) having full or partial control of the IUT and observing its behaviour. The Test System and the IUT are usually connected over at least one single interface.

The Test System can usually access the lower layers of the IUT in order to check the protocol messages generated, and may get access upper layers of the IUT in order to have more control of it, and sometimes get relevant information for the tests.




Figure 3. Detailed General Conformance Testing Architecture

Page 12 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

Conformance testing provides a high degree of control and observation of the IUT, even provoking and testing non-normal scenarios and error behaviours. In addition, conformance testing gives a high level of confidence that the standardized functionality of a product is working as specified. This confidence is achieved because conformance tests are detailed, they focus on single requirements and they can be executed in an automated and repeatable manner under controlled conditions.

Conformance testing does not necessarily prove interoperability with other products. Depending on how precisely the technical specification (or standard) has been written, it may be open to multiple interpretations, meaning that implementations from different vendors might be compliant but may not fully interwork. From an end-user perspective these devices might just have well have been implemented according to proprietary specifications. Good technical specifications are unambiguous and leave no margin for misinterpretation, but conformance test specifications developed from a poorly written base standard may lead to products which conform to the standard but do not interoperate.

Conformance testing has historically been seen as an expensive tool, especially for radio environments such as GSM or DECT. Of late this perception has changed with organizations like ETSI working to improve the test specification development process through methodology improvements and test languages such as TTCN-3.

TTCN-3 provides both a standardized language for test cases and an architecture for developing test systems. TTCN-3 is now widely used as a testing language for standards such as WiMAX and LTE in telecommunications, and it is even used in ITS (Intelligent Transport Systems). TTCN-3 is mostly used for protocol testing but other test areas (software, system, etc.) and verification objectives (interoperability, robustness, etc.) are starting to use TTCN-3. PowerUp uses TTCN-3 for the test cases implementation.

2.2. PowerUp Implementations Under Test

Within PowerUp two different IUTs are clearly identified: the EVCC (Electronic Vehicle Communication controller) as part of the A-V2G, and the SECC (Supply Equipment Communication Controller) as part of the I-V2G. From the protocol point of view, a "client-server" model is used, where the EVCC takes the role of the "client" of the protocol, initiating the communications, and the SECC takes the role of the "server".

Page 13 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

These two IUTs implementations (specified in WP4 and implemented in WP5) are based on the ISO/IEC 15118-2 standard, and more concretely the application layer protocols: **SECC Discovery Protocol (SDP) and V2G protocol (pV2G)**. The underlying protocols, such as V2GTP, UDP, TCP, etc., are out of scope for the PowerUp conformance test specifications. The conformance test specifications developed in PowerUp are focused on SDP and pV2G.

2.3. ETSI testing methodology

The main objective of this work is to define a formal procedure to develop a complete set of test specifications in order to:

- Ensure that equipment and systems claiming compliance to the standard have been sufficiently tested to demonstrate that compliance.
- Guarantee that equipments from multiple vendors have been tested the same way, to the same interpretation of the standard, thus increasing the interoperability of the equipment.

The conformance test methodology followed in WP6 is based on the ITS framework [4] and ETSI recommendations. This methodology is divided into different activities as shown in Figure 4.




Figure 4. Conformance Test Methodology

- Activity 1 Production of the PICS proforma: PICS provides an overview of the features, capabilities, functionalities and options that are supported by a IUT conforming to the ISO/IEC 15118-2 standard.
- Activity 2 Development of the Test Suite Structure and Test Purpose (TSS & TP): Test Purposes (TPs) provides a short description of each test objective using words, focusing on the meaning of the test rather than detailing how it may be achieved. TSS provides a logical grouping for the TPs.
- Activity 3 Development of the ATS (Abstract Test Suite): An ATS is a collection of Test Cases. Each Test Case specifies the preconditions for setting up the test and the steps that must be taken in order to perform the test. As previously discussed, TTCN-3 is the language selected and used for writing the test cases.

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

 Activity 4 - Development and Validation of the Test System: The test cases developed in activity 3 must run on a test system, and must be validated against samples which implement the ISO/IEC 15118-2 standard.

The PowerUp Conformance Test Specification is composed of the following documents:

- PICS Document (See Section 3.1)
- TSS & TP Document (See Section 3.2)
- ATS document (See Section 3.3)
- Test System Document (See Section 4).

This test specification is extracted from ISO/IEC 18115-2, and specifically DIS_Candidate 3.

3. V2G TEST SPECIFICATIONS

3.1. Protocol Implementation Statement Conformance (PICS)

The purpose of the PICS proforma is to provide a mechanism whereby a supplier of an EVCC or a SECC claiming to meet the requirements defined in ISO/IEC 15118-2 [1] may provide information about the implementation in a standardized manner.




Figure 5. Elements for PICS development

The complete set of PICS for the EVCC and the SECC have been defined in Annex A using a tabular format shown in the next table.

Item	Feature	Reference	Status	Mnemonic	Support
[x]	[Feature]	[Section]	[M o o.iX]	[Mnemonic]	[Y N]

Page 16 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

Where each column has the following purpose;

- **Item:** a number which identifies the item in the table.
- Feature: a free text representation of each respective item (e.g. parameters, timers, etc.). It implicitly means "is <feature> supported by the implementation?".
- Reference: reference to clauses in ISO 15118-2 [6] relevant to the feature (except where explicitly stated otherwise).
- **Status:** Optionality status of the feature. The following notations are used;
 - o M (mandatory): the capability MUST be supported.
 - o O (optional): the capability MAY be supported.
 - O.X (qualified optional) for mutually exclusive or selectable options from a set. "X" is an integer which identifies a unique group of related optional items and the logic of their selection which is defined immediately following the table.
- Mnemonic: a key word that is used in conditional status expressions as a Boolean value which is true if the item identified by the mnemonic is supported and false in any other case.
- Support: filled in by the supplier of the implementation to indicate if a particular implementation supports the feature. The following common notations are used for the support column:
 - o Yes Supported by the implementation.
 - o No Not supported by the implementation.

The PICS proforma is subdivided into 8 categories which can contain sub clauses:

- Category 1 V2G Entity Role: this category identifies what role is implemented by the IUT (either EVCC or SECC).
- Category 2 Charging Mode: this category indicates what charging modes are supported: AC or DC. One of these two modes MUST be supported.
- Category 3 Identification Mode: this category indicates what identification modes are supported: EIM or PnC. One of these two modes MUST be supported.

Page 17 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

- Category 4 Optional Sets: this category represent a set of capabilities that the IUT could support or could not related to Value Added Services and Certificates.
- Category 5 Protocol Stack: this category indicates what protocols are supported.
- Category 6 SECC Discovery Protocol (SDP): this category is specific to the SDP protocol, and indicates what features are supported by the IUT.
- Category 7 V2G Application Layer Protocol Handshake: this category is specific for the Handshake protocol, and indicates what features are supported by the IUT.
- Category 8 V2G Application Layer Messages: this category is specific for the V2G protocol, and indicates what features are supported by the IUT.

3.2. Test Suite Structure and Test Purposes (TSS&TP)

The aim of the Test Purposes (TPs) is to provide a short description of each test objective using natural or pseudo language (i.e. TPLan, a standardized notation for expressing test purposes), focusing on the meaning of the test rather than detailing how it may be achieved; Test Suite Structure (TSS) provides a logical and structured grouping of the TPs.




Figure 6. Generic Test Suite Structure

Around 150 test purposes have been specified in PowerUp and can be found in Annex B and Annex C.

|--|




Figure 7. Elements for TSS&TP development

3.2.1 Test Suite Structure

Defining the Test Suite Structure requires the grouping of the Test Purposes according to some criteria.

The Test Suite Structure is structured as a tree divided into two levels. The higher level represents the protocol to be tested, either SDP or V2G (hereinafter called Application Layer Messages). The lower level, in case of SDP, represents the difference in term of the role implemented in the SDP protocol; either client or server. For Application Layer Messages, the second level identifies the different states of the V2G protocol.

The following table shows the TSS specified.

Table 1. Test Suite Structure

Group	Sub-group
SECC Discovery Protocol	Client
	Server
Application Layer Messages	Handshake Protocol
	Session Setup
	Session Discovery
	Service Detail
	Service and Payment Selection
	Certificate Update
	Certificate Installation
	Payment Details


	Page 19 of 172
--	----------------

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

Contract Authentication
Charge Parameter Discovery
Power Delivery
Session Stop
Charging Status
Metering Receipt
Cable Check
Pre Charging
Current Demand
Welding detection

3.2.2 Test Configurations

This section introduces the test configurations that have been used for the definition of test purposes. The test configurations cover the various scenarios of ISO/IEC 15118-2 [1]. The test configuration elements are:



Test Configuration 1: CF01

The EVCC connects to the SECC directly establishing an end to end connection based on V2G protocol. In this case the EVCC is the IUT.



 $\ \, \textbf{Figure 8. Test configuration 1} \\$

Test Configuration 2: CF02

Page 20 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

The EVCC connects to the SECC directly establishing an end to end connection based on V2G protocol. In this case the SECC is the IUT.



Figure 9. Test configuration 2

Test Configuration 3: CF03

This configuration is used for a special case in SDP (SECC Discovery Protocol) testing. In this configuration the IUT and EVCCNodeA connect to the SECC.




Figure 10. Test configuration 3

3.2.3 Test Purpose Identifier Naming Convention

The TP identifier serves to uniquely identify a test purpose. The naming convention ensures uniqueness of the TP identifier.

The identifier of the TP is built according to the following table.

Table 2. Test Purpose Identifiers

Identifier:	TP/ <ent>/<gr>/<sgr>/<x>/<nn></nn></x></sgr></gr></ent>		
	<ent> = entity</ent>	EVCC	
		SECC	
	<gr> = group</gr>	SDP	SECC Discovery Protocol
		ALM	Application Layer

	Page 21 of 172
--	----------------

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

		Message
<sgr> = sub-group</sgr>	CLI	Client
	SRV	Server
	НР	Handshake Protocol
	SSE	Session Setup
	SDI	Session Discovery
	SDE	Service Detail
	SPS	Service and Payment Selection
	CU	Certificate Update
	CI	Certificate Installation
	PDT	Payment Details
	CA	Contract Authentication
	CPD	Charge Parameter Discovery
	PWD	Power Delivery
	SST	Session Stop
	CHS	Charging Status
	MR	Metering Receipt
	ССК	Cable Check
	PCH	Pre Charging
	CD	Current Demand
	WD	Welding detection
<x> = type of testing</x>	BV	Valid behaviour tests
	ВО	Inopportune behaviour
	BI	Invalid Syntax o Behaviour tests
<nn> = sequential number</nn>		01 to 99

	Page 22 of 172
	Page 22 of 1/2

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

3.2.4 Test Purpose Template

A test purpose is an informal description of the expected test behavior. As such it is written in prose.

Several types of presentation of the test purposes are possible. These include combining text with graphical presentations, mainly tables, and sometimes include message sequence charts.

The template for specifying the TP follows a tabular format as the ITS framework [4] suggests, using recommendations concerning the wording and the organization of the TPs.

In addition, it is important to remark that the TP Behaviour has been written using a formal language so-called TPLan specified by ETSI.

Table 3. Test Purpose Template

TP Header		
TP ID	The TP ID is a unique identifier. It is specified according to the TP	
	naming conventions defined in the above sub-clause.	
Test objective	Short description of test purpose objective according to the	
	requirements from the base standard.	
Reference	The reference indicates the sub-clauses of the reference standard	
	specifications in which the conformance requirement is expressed.	
Reference	The reference requirement indicates the sub-clauses of the reference	
requirement	standard specification requirement.	
Config Id	The Config Id references the ISO/IEC 15118-2 configuration selected for	
	this TP	
PICS Selection	Reference to the PICS statement involved for selection of the TP.	
	Contains a Boolean expression.	
	TP Behaviour	
Initial conditions	The initial conditions define which state the IUT has to be to apply the	
	actual TP. In the corresponding Test Case, when the execution of the	
	initial condition does not succeed, it leads to the assignment of an	
	Inconclusive verdict.	
Expected	Definition of the events, which are parts of the TP objective, and the IUT	
behaviour (TP	are expected to perform in order to conform to the base specification. In	
body)	the corresponding Test Case, Pass or Fail verdicts can be assigned	
	there.	

Defining the initial conditions, separately from the expected behavior, makes the reading of the TP easier and avoids misinterpretation.

Two TPs are provided as examples of how this template should be used.

D 22 -f 172
Page 23 of 172
1

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

Table 4. Test Purpose - Example 1

```
TP Id
                    TP/EVCC/ALM/SSE/BV/01
  Test objective
                    Checks Session Setup Request message is sent after receiving
                    SupportedAppProtocol Response message
    Reference
                    ISO/IEC 15118-DIS-2, section 8.4.1.2.2
                    [V2G2-184], [V2G2-185], [V2G2-186], [V2G2-187], [V2G2-188]. [V2G2-189]
    Reference
  requirement
    Config Id
                    CF01
 PICS Selection
                                   Initial conditions
with {
       the IUT having sent SupportedAppProtocol Request message
                                  Expected behaviour
ensure that {
            when {
                  the IUT receives the SupportedAppProtocol Response message
                       containing ResponseCode field indicating value
                       'OK_SuccessfullNegotiation'
            \label{eq:then} \} then \{
                  the IUT sends a Session Setup Request message
                     containing a valid Header
                     containing a Body
                        containing EVCCID field
                     before V2G_EVCC_Sequence_Performance_Time expires
            }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

Table 5. Test Purpose - Example 2

TP Id	TP/SECC/ALM/SDI/BV/01
Test objective	Checks Service discovery Response message is sent after receiving
	Service discovery Request message
Reference	Section 8.4.1.3.3
Reference	[V2G2-195], [V2G2-196], [V2G2-543], [V2G2-544]
requirement	
Config Id	CF02
PICS Selection	PICS_SECC
	Initial conditions
with {	
the IUT hav	ring sent Session Setup response message
}	
	Expected behaviour
ensure that {	
when {	
t	the IUT receives the Service discovery Request message
	}
then {	
t	the IUT sends a Service Discovery Response message
	containing a valid Header
	containing a Body
	containing Response code indicating value 'OK'
	containing PaymentOption type field
	containing Charge Service
	containing service type
	containing Service Tag
	containing Service ID field
	containing Free Service field
	containing EnergyTransfer type field
	containing Service list
	/2G_SECC_Sequence_Perfomance_Time expires
}	
}	

3.3. Abstract Test Suite (ATS)

The last phase of the test specification is the detailed description of each test case or Abstract Test Suite (ATS). The ATS is a collection of detailed test cases or scripts that implement the test purposes. The ATS specifies HOW to test and assign test verdicts. Although ATS and Test Systems get usually mixed up, they have different roles; The ATS is focused on the IUT behavior, whereas the test system handles test case management, message encoding and decoding, adaptation layers, transporting, etc.




Figure 11. Elements for ATS development

3.3.1 Point of Control and Observation

It is necessary to identify the points in the test environment where the test events have to be controlled and observed. These points are called Points of Control and Observation (PCOs).

After analysing the TSS&TP (Annex B and Annex C), two PCOs have been identified, one associated with the SECC Discovery Protocol called PCO.SDP, and the other associated to the V2G message protocol and so-called PCO.V2Gproto.

The table below summarises the two PCOs associated with their corresponding test events;

РСО	Protocol Under Test	Test Events
PCO.SDP	SDP	SDP messages
PCO.V2Gproto	V2G protocol	V2G messages

Table 6. Points of Control and Observation

The following diagram depicts an OSI model representation of the PowerUp terminal device in all of the scenarios were IEC/ISO 15118-2 is involved.

	Page 26 of 172
--	----------------




Figure 12. PCOs' location

3.3.2 V2G Abstract Protocol Tester

The abstract protocol tester is a process that provides behaviours for testing an IUT by emulating a peer IUT at the same layer, and enabling to address a single test objective.

The TSS&TP is grouped into two groups; one addressing the SDP protocol, and the other the V2G application layer protocol. Therefore two abstract protocol testers have been specified according to the protocol to be tested.

Each Abstract Protocol Tester is based on the Abstract Protocol Tester defined in the ETSI EG 202 798 [4]. These abstract protocol testers are shown below for each protocol;




Figure 13. Abstract Protocol Tester for V2G Application Layer protocol




Figure 14. Abstract Protocol Tester for Session Discovery protocol

As the figure above illustrates, the corresponding ATS needs to use lower layers to establish a proper connection to the system under test (SUT) over a physical link (Lower layers link). The lower layer for SDP is based on V2GTP over UDP, and the lower layer for V2G messages is V2GTP over TCP.

3.3.3 V2G General Test Architecture

The approach for the implementation of the Abstract Protocol Tester selected in PowerUp follows the recommendation of the EG 202 798 where the **TTCN-3 language and its architecture** are recommended (see Annex F for further information about TTCN-3 language). TTCN-3 and its architecture have been already successfully used in other ITS protocols such as GeoNetworking, CAM (Cooperative Awareness Messages), etc.

Following this recommendation the PowerUp tester architecture comprises a non-technology dependent *Test Suite*, and a technology dependent *Test Platform*.




Figure 15. High level V2G Test Architecture

- TTCN-3 Test Suite for PowerUp: the test suite is platform independent, and it is the cornerstone of the architecture. It allows a complete decoupling between test suites and the rest of the tester. The test suite is composed of a complete set of test cases covering application layer requirements specified by [1].
- TTCN-3 Test Platform for PowerUp: this is the platform dependent part that includes adaptors and drivers. This part of the architecture definition depends on the specific platform (e.g., Windows or Linux) on which the tester is going to run.

3.3.4 V2G Test Architecture Design

By following EG 202 798, the V2G test architecture can be integrated into the existing ETSI ITS test platform. This allows the efficient use of the existing platform as well as allowing it to be enriched.

Figure 16 shows the TTCN-3 test architecture design used for the V2G ATS. The Test Suite must interact with the Test Platform to implement the collection of TTCN-3 test cases that are intended to be used to test the PowerUp IUTs.

The V2G TTCN-3 test cases implement the test algorithms specified in the TSS&TP document, including verdict logic that allows pass/fail diagnosis.

The test algorithms use the PCOs identified in section 3.3.1 (PCO.SDP and PCO.V2Gproto) in order to

- 1) control the test event to be sent towards the IUT, and
- 2) observe the test events received from the IUT.

Page 29 of 172	
----------------	--

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

In TTCN-3 these two PCOs have been implemented through a logical TTCN-3 concept called port (v2gPort) which allows SDP and V2G message exchange with the IUT.




Figure 16. V2G Test Architecture

The SDP and V2G messages have been mapped into TTCN-3 structure. Through this mapping, the TTCN-3 is able to build and send these messages, as well as receive them via the v2gport.

Additionally, the test cases are able to control and configure the test platform through a dedicated port called acPort.

To build up a tester, the test platform must be also developed (see Section 4). This test platform is composed of three adaptation layers:

Pa	age 30 of 172
----	---------------

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

- PA (Platform Adaptor) layer functionality implements the communication between the TTCN-3 modules and external elements that constitute the test tool such as reference node implementations, timers, external functions, etc. The External functions are a powerful resources supported by TTCN-3 language. An External function is a function declared at the TTCN-3 level but implemented at the native level.
- <u>SA (System Adaptor) layer</u> functionality is divided into two modules:
 - v2G lower layer stack module implements the communication with the IUT and carries out either the SDP or the V2G message sent to or received from the IUT. In case of SDP, this module is based on V2GTP over UDP; and in case of V2G message, the module is based on V2GTP over TCP.
 - Upper Tester Transport module implements functions that enable triggering V2G functionalities by simulating primitives from other entities such as smart meters, load balancing controller, etc in the SUT.
- CODECS layer is the part of the tester to encode and decode messages between the TTCN-3 internal data representation and the format required by the related base standard. Two CODECS are required in this tester, one for SDP, and one for V2G messages.

Further description of these layers is provided in section 4.3.

3.3.5 Ports and Primitives

The PowerUp Test Suite implements three ports to be used by the V2G ATS:

- The V2Gport
- The utPort
- The acPort

3.3.5.1 V2Gport

This port is used to send and receive the following message sets;

- SECC Discovery Protocol messages in accordance with ISO/IEC 15118-2 standard.
- V2G Handshake Protocol messages in accordance with ISO/IEC 15118-2 standard.

	Page 31 of 172
--	----------------

PowerUp Final V2G Architecture	Public	Copyright PowerUp	
		Contract N. 285285	

 V2G application layer protocol messages in accordance with ISO/IEC 15118-2 standard.

Two primitives are currently defined for this port:

- 1) The V2Greq primitive to send SDP, V2G Handshake and V2G application layer messages to the IUT. Depending on the IUT to be tested:
 - a. If the IUT is an EVCC, the messages sent by the tester will be the messages associated with the SECC role, thus response messages such as SessionSetupRes, ServiceDiscoveryRes, etc.
 - b. If the IUT is a SECC, the messages sent by the tester will be the messages associated with the EVCC role, thus request messages such as SessionSetupReq, ServiceDiscoveryReq, etc.
- 2) The V2Gind primitive to receive SDP, V2G Handshake and V2G application layer protocol messages from the IUT. Depending on the IUT to be tested:
 - a. If the IUT is an EVCC, the messages received by the tester will be messages associated with request messages.
 - b. If the IUT is the SECC, the messages received by the tester will be messages associated with response messages.

Primitive	TTCN-3 Message	Direction	IUT
	SDP Request		
	Handshake protocol Request	→	SECC
V2C==	V2G message Request		
V2Greq	SDP Response		
	Handshake protocol Response	→	EVCC
	V2G message Response		
V2Gind	SDP Request	(EVCC

Page 32 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

Handshake protocol Request		
V2G message Request		
SDP Response		
Handshake protocol Response	-	SECC
V2G message Response		

3.3.5.2 utPort

The utPort has been included in the V2G ATS in order to be able to stimulate the IUT and receive extra information from IUT upper layers.

The utPort is not used in the current implementation and is provided for future expansion.

3.3.5.3 acPort

The acPort has been included in the V2G ATS in order to be able to control and configure the test adapter for specific cases.

The acPort is not used in the current implementation and is provided for future expansion.

3.3.6 TTCN-3 Test Cases

TTCN-3 test cases have been mostly structured into two groups; one focuses on the test cases related to the EVCC, and the other focuses on the SECC. Each group implements SDP and V2G application layer protocol test cases specified in the TSS&TP document.

The diagram below shows the test case architecture which has been defined for the implementation of all test cases:

Page 33 of 172
1 age 33 of 172




Figure 17. Test case architecture

- Test Configuration: this step configures and activates the TTCN-3 ports to be used during the test case. In addition, if the test platform requires any specific configuration, this is done in this phase.
- Preamble: this step implements the 'Initial conditions' indicated in the test purpose. During this phase, the test case brings the IUT into a state from which the test body will start.
- Test Body: this step implements the 'Expected behavior' description indicated in the test purpose. During this phase the test case analyzes the sequence of messages to be exchanged between the tester and the IUT, checking the messages sent by the IUT, and stimulating the IUT by sending specific messages. In addition, the test verdict is assessed at the end of this phase.
- Postamble: this step finalizes the test case in a proper way so that IUT is ready for further test cases.

As indicated above, the preamble brings the IUT up to a V2G application protocol state which the test body will start from. The test suite must be able to emulate the behavior of the ISO/IEC 15118-2 protocol both from the SECC perspective when the IUT is an EVCC, and from the EVCC perspective when the IUT is a SECC.

The preamble has been divided into two phases. The first phase addresses the common charge protocol states, which are independent of the selected charge mode; the second phase is specific to the selected charge mode (AC or DC).

Public	Copyright PowerUp
	Contract N 285285

The common part covers the following charge protocol states: SDP, Supported Application Protocol, Session Setup, Service Discovery, Service Details, Service and Payment Selection, Certificate Update, Certificate Install, Payment Details, Contract Authentication and Charge Parameter Discovery.

PowerUp Final V2G Architecture

The specific part for AC charge mode covers the following charge protocol states: Power Delivery, Charging Status, Metering Receipt and Session Stop.

The specific part for DC charge mode covers the following charge protocol states: Cable Check, Pre Charge, Power Delivery, Current Demand, Welding Detection and Session Stop.

In addition, the behavior of the preamble is controlled by specific conditions which indicate if either the EVCC emulator or the SECC emulator should emulate either a specific behavior or following a normal behavior, for instance: send a FAILED response code in a Service Discovery Response after receiving a Service Discovery Request.

The general pseudo-code for the preamble implementation is described below:

```
CurrentChargeState = InitialChargeState;
While (CurrentChargeState != EndChargeState)
{
        If not message received belonging to CurrentChargeState then
                FAIL;
        else
        {
                Process message received;
                Send reply message belonging to CurrentChargeState depending on the specific conditions;
                CurrentChargeState = NextChargeState;
        }
An example of a TTCN-3 test case is shown below:
testcase TC_EVCC_ALM_SDI_BV_01() runs on ItsV2G system ItsV2Gsystem {
        // Local variables
        // Test control
      // Test component configuration
      f_cfUp();
      // Test adapter configuration
      // Preamble
        f_prV2G_secc_common(e_sessionSetup,e_noConditions);
```

```
// Test Body
        tc_v2g_secc_sequence_timer.start;
           [] v2gPort.receive(mw_v2gInd (
        mw_v2gMsg(mw_v2gHeader(vc_sId),mw_serviceDiscoveryRequest_generic))) {
                tc_v2g_secc_sequence_timer.stop;
           log("*** TC_EVCC_ALM_SDI_BV_01: PASS: V2G Service Discovery request message received BEFORE
expiry of the sequence performance timer***");
          setverdict(pass);
        [] tc_v2g_secc_sequence_timer.timeout {
                 log("*** TC_EVCC_ALM_SDI_BV_01: FAIL: V2G Service Discovery request message not
                received ***");
          setverdict(fail);
        }
      }
      // Postamble
      f_poDefault();
      f_cfDown();
}// end TC_EVCC_ALM_SDI_BV_01
```

The naming conventions used for the V2G ATS are based on the ITS framework [4] and ETSI recommendations. See Annex D for details.

4. V2G CONFORMANCE TEST PLATFORM

The purpose of the V2G conformance test platform is to provide a reliable set of software and hardware that can be used to validate TTCN-3 abstract test suites (ATS) developed in this project.

4.1 Constraints

The architecture of this test platform has been designed with respect to the following constraints:

- To be independent of the platform used to implement the test system;
- To be independent of the TTCN-3 tool provider;
- To be configurable and customizable;

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

- To provide tools and well defined interfaces to the system under test (SUT), allowing test automation;
- To be easily extensible for future protocol modification;
- To provide generic components that can be reused in other test platforms.

In order to ensure independence of hardware platforms, all software components running on the test platform have been implemented using $Java^{TM}$, using generic and widely used libraries.

Test tool independence has been achieved by isolating the tool specific interfaces from core functionalities of the platform. Adapting the current platform to a different test tool would only require the implementation of a very simple piece of software mapping tool-specific functions to generic functions defined in this project.

In addition, great care has been taken to separate PowerUp specific functionalities from generic test platform tasks in order to provide a maximum number of reusable components for future test platforms.

4.2 Hardware and test tool

Besides the components already shown in Figure 16, another two components should be considered when implementing the test platform:

- The hardware supporting TTCN-3 test execution and adaptation to SUTs;
- The TTCN-3 test tool providing the necessary software to execute the abstract test suites;

The main hardware component of the V2G test platform is a standard PC. Its role is to host the execution of the test suites using a commercial TTCN-3 test tool.

Whatever operating system is installed on the computer, it is necessary to ensure that the following points are taken into account:

- No firewall interference with traffic generated by the Test System and/or SUT
- Time synchronization between the SUT and the test system
- Test system processes (especially the test adapter) have to be granted unrestricted control to telecommunication hardware

Page 37 of 172	
Page 37 of 172	
I Page 37 of 172	
	I Page 37 of 172
1 dgc 37 01 172	1 490 37 01 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

The TTCN-3 test tools are usually provided by commercial companies and their description is out of the scope of this document. The implementation details of the other components are described in the following sections.

4.3 Codecs

The codec entity is responsible for the encoding and decoding of TTCN-3 abstract values into bitstrings suitable to be sent to the System Under Test (SUT).

In order to simplify implementation and to ease maintenance, coding and decoding tasks are handled by several codecs:

- One independent codec per protocol (SDP, Supported Application Protocol and V2G application protocol);
- One codec for TTCN-3 types that do not correspond to real protocol messages. It includes for example all auxiliary types used to carry information to/from Test Adapter, like the ones defined in TestSystem modules (V2Gind, V2Greq, ...).

For protocol messages defined using XSD schemes, usage of dedicated commercial XSD tools is recommended. XML messages also require EXI compression to be used. For this purpose and EXI helper using Exificient¹ library has been developed.

Selection of correct codec for encoding a message at runtime is dictated by means of the "with encode" statement within TTCN-3 modules. For instance the following statement:

```
with {
  encode " LibItsV2G_TypesAndValues"
}
```

will cause org.etsi.its.codec.ttcn.LibItsV2G_TypesAndValuesCodec to be invoked.

4.3.1 Advanced details

The figure below gives an overview of the relations between the different java classes implementing the codec. The structure is relatively simple. Connection with the tool-

http://exificient.sourceforge.net

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

dependent classes is realized through the ICodec interface and is not depicted in this figure.




Figure 18. Relationship between CODECS java classes

Each codec implements the standard TCI interface TciCDProvided as described in [6]. In addition, codecs have to implement the ICodec interface, which provides a toolindependent instantiation of an API to TTCN-3 tools.

The BaseCodecImpl class implements the minimal functionalities of a codec and is used as a base class for further codec development. For extensibility purpose, this class is not ITS-specific, and it can be used as-is in other platform projects.

The ItsCodecImpl class directly extends BaseCodecImpl and provides ITS common codec functionalities. Each PowerUp codec derives from this class.

4.4 Test Adapter

The test adapter is conceptually splits into three parts:

- a lower test adapter
- a TTCN-3 platform adapter implementing timers
- an upper test adapter

Page 39 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

4.4.1 Lower Tester

TTCN-3 test suites are usually focussed on a single protocol layer and designed to be executed against real implementations (IUT). However, it is unusual to find standalone implementations as they are commonly integrated as an internal component of a physical device (SUT).

The purpose of a lower test adapter is to prepare and adapt the protocol messages used by TTCN-3 test suites so that they can be transmitted successfully to the SUT. One way to achieve this goal is, for example, to implement lower layers and encapsulate protocol messages accordingly. For instance, SDP messages need to be encapsulated in UDP datagrams. The higher up the IUT is located in the OSI stack, the more complex the test adapter.

For PowerUp, and in the field of conformance testing, SDP messages shall be transferred using UDP/IPv6 datagrams and V2G application layer messages shall be transferred over a TCP/IPv6 connection. To achieve this purpose, the Test Adapter has been implemented as follows:

- If Test System is acting as a SECC:
 - Handling of SDP messages:
 - Join IPv6 multicast group "all-nodes multicast" (FF02::1)
 - Open a UDP socket for incoming datagrams on well-known port 15118 and wait for messages
 - Send all outgoing SDP messages to the SUT using link-local address or global address of Test System, depending on SUT's first message.
 - Transfer received message on this socket to Test Management
 - Handling of V2G application layer messages:
 - Open TCP socket using port and address specified in TTCN-3 module parameters PXT_SECC_IP_ADDRESS and PXT_SECC_PORT
 - Wait for incoming connection requests
 - Send outgoing V2G messages using pre-established connection

Page 40 of	f 172
------------	-------

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

- Transfer received message on this socket to Test Management
- If Test System is acting as EVCC:
 - o Handling of SDP messages:
 - Send first SDP message to IPv6 "all-nodes-multicast" address (FF02::1) on well-known UDP port 15118
 - Record SUT's address on its first response
 - Send following SDP messages to SUT's address
 - Transfer received message on this socket to Test Management
 - o Handle V2G application layer messages:
 - Initiate TCP/IPv6 connection using port and address specified in TTCN-3 module parameters PXT_SECC_IP_ADDRESS and PXT_SECC_PORT
 - Send outgoing V2G messages using this connection
 - Transfer received message on this socket to Test Management

All connections and communication sockets are closed after execution of each test case.

4.4.2 Platform Adapter

All TTCN-3 commercial tools provide generic Platform Adapter implementations for managing TTCN-3 timers. These implementations are well tested and usually accurate enough for most uses. In the case of PowerUp protocols, the protocol timer value is in the order of thousands of milliseconds. This can be handled well with the built in test system timers. As a consequence no specific development is required for this component.

4.4.3 Upper Tester

The upper tester is used to interact with the upper interface of the implementation under test (IUT). It is typically used for:

- Initializing SUT
- Triggering events in SUT
- Triggering messages

All Upper Tester primitives are implemented within the upperTesterPort module.

Page 41 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

5. CONCLUSIONS

This deliverable contains the conformance test specifications for ISO/IEC15118-2 standard which have been developed by following the ISO 9646 testing methodology and ETSI recommendations.

These conformance test specifications consist of three parts:

- 1) Protocol Information Conformance Statements (PICS) which permits a supplier to provide information about their products or implementations.
- 2) Test Suite Structure and Test Purposes (TSS&TP) which provides in a structured manner a short description of each test objective. Around 150 test purposes have been written.
- 3) Abstract Test Suite (ATS) which provides a collection of test cases or scripts which implement the test purposes. These tests have been written by using TTCN-3, an international and standardized testing technology specifically designed for testing and certification.

In addition, the V2G conformance test platform has been developed in order to provide reliable test scripts. After test scripts validation, the conformance test platform may be used to run the conformance tests against V2G implementations so that vendors can assess the level of compliance of their equipments. Further use of the conformance test platform might be certification and in-house testing purposes.

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

REFERENCES

- [1] ISO/IEC CD 15118-2 Road vehicles Vehicle-to-Grid Communication Interface Part 2.
- [2] PowerUp Delivery 4.1: V2G Interface specifications between the electric vehicle, the local smart meter, and ITS service providers (2012-06).
- [3] PowerUp Delivery 6.2: V2G Interoperability testing framework (2012-12).
- [4] ETSI EG 202 798: Intelligent Transport Systems (ITS); Testing; Framework for conformance and interoperability testing (2011-01).
- [5] PowerUp Delivery 5.1: Automotive prototyping of V2G adapters (2012-12).
- [6] ETSI ES 201 873-6 4.4.1 TTCN-3: TTCN-3 Control Interface
- [7] PowerUp Delivery 3.2: Final V2G Architecture (2012-09).

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

ANNEX A: PROTOCOL IMPLEMENTATION CONFORMANCE STATEMENTS (PICS)

A.1 V2G Entity Role

Table A.1: V2G Entity Role

Item	Role	Reference	Status	Mnemonic	Support
1	EVCC	1	0.101	PICS_EVCC	
2	SECC	1	0.101	PICS_SECC	

o.101: It is mandatory to support at least one of these roles.

A.2 Charging Mode

Table A.2: Charging Modes

Item	Mode	Reference	Status	Mnemonic	Support
1	AC	8.5.3	0.201	PICS_AC	
2	DC	8.5.4	o.201	PICS_DC	

o.201: It is mandatory to support at least one of these modes.

A.3 Identification Mode

Table A.3: Identification Modes

Item	Mode	Reference	Status	Mnemonic	Support
3	EIM	8.6	0.302	PICS_EIM	
4	PnC	8.6	0.302	PICS_PnC	

o.301: It is mandatory to support at least one of these modes.

A.4 Optional Sets

Table A.4: Optional Sets

Item	Set	Reference	Status	Mnemonic	Support
1	Value Added Service	8.6	0	PICS_VAS	
2	Certification Update	8.6	c.401	PICS_CU	
3	Certification Installation	8.6	c.402	PICS_CI	

c.401: IF PICS_PnC THEN o ELSE n/a

	Page 44 of 172
--	----------------

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

c.402: IF PICS_PnC THEN o ELSE n/a

A.5 Protocol Stack

Table A.5: Protocol Stack

Item	Protocol	Reference	Status	Mnemonic	Support
1	Application Layer Messages and Handshake	8	m	PICS_ALM	
2	SDP	7.10	m	PICS_SDP	
3	EXI	7.9	m	PICS_EXI	
4	V2GTP	7.8	m	PICS_V2GTP	
4	TLS	7.7	c.501	PICS_TLS	
5	ТСР	7.7	m	PICS_TCP	
6	UDP	7.7	m	PICS_UDP	
7	IPv6	7.6.2.1	m	PICS_IPv6	
8	ICMPv6	7.6.2.4	m	PICS_ICMPv6	
9	SLAAC	7.6.3.2	m	PICS_SLAAC	

c.501: IF (PICS_EVCC AND PICS_EIM AND NOT PICS_VAS) THEN o ELSE m

A.6 SECC Discovery Protocol (SDP)

Table A.6.1: SDP role

Item	Name	Reference	Status	Mnemonic	Support
1	Client	7.10.1	c.601	PICS_SDP_cli	
2	Server	7.10.1	c.602	PICS_SDP_srv	

c.601: IF PICS_EVCC THEN m ELSE n/a

c.602: IF PICS_SECC THEN m ELSE n/a

Table A.6.1: SDP PDU

Item	Name	Reference	Status	Mnemonic	Support
1	SECC Discovery Request	7.10.1.4	m	PICS_SECC_Dis_Req	
2	SECC Discovery Response	7.10.1.5	m	PICS_SECC_Dis_Res	

Table A.6.2: SDP Features

	Page 45 of 172
--	----------------

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

Item	Name	Reference	Status	Mnemonic	Support
1	Retransmission Handling	7.10.1.6	c.801	PICS_SECC_Dis_rtx	
2	Security Negotiation for Transport Protocol	7.10.1.7	m	PICS_SECC_Dis_sec	

c.801: IF PICS_EVCC THEN m ELSE n/a

A.7 V2G Application Layer Protocol Handshake

Table A.7.1: Application Protocol Handshake messages

Item	Name	Reference	Status	Mnemonic	Support
1	supportedAppProtocolReq	8.2.2	m	PICS_sAPReq	
2	supportedAppProtocolRes	8.2.2	m	PICS_sAPRes	

Table A.7.2: Handshake features and error handling

Item	Name	Reference	Status	Mnemonic	Support
1	Protocol selection	8.2.2	c.Hiba! A hivatkozási forrás nem található.01	PICS_ProtSel	
2	Minor protocol version deviation	8.2.2	m	PICS_MinorProtVDev	
3	No protocol agreement	8.2.2	m	PICS_NProtAgr	

c.801.01: IF PICS_SECC THEN m ELSE n/a

A.8 V2G Application Layer Messages

Table A.8: V2G Application Layer Features

Item	Feature	Reference	Status	Mnemonic	Support
1	Session Setup	8.4.1.2.2	m	PICS_SSE	
2	Service Discovery 8.4.1.3.2 m PICS_SDI				
3	Service Detail	8.4.1.4.2	c.1101	PICS_SDE	
4	Service and Payment Selection	8.4.1.5.2	m	PICS_SPS	
5	Payment Details	8.4.1.6.2	c.1102	02 PICS_PDT	
6	Contract Authentication	8.4.1.7.2	m	PICS_CA	
7	Charge Parameter Discovery	8.4.1.8.2	m	PICS_CPD	

Page 46 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

8	Power Delivery	8.4.1.9.2	m	PICS_PWD	
9	Certificate Update	8.4.1.10.2	c.1103	PICS_CU	
10	Certificate Installation	8.4.1.11.2	c.1104	PICS_CI	
11	Session Stop	8.4.1.12.2	m	PICS_SST	
12	Charging Status	8.4.2.2.2	c.1105	PICS_CHS	
13	Metering Receipt	8.4.2.3.2	c.1106	PICS_MR	
14	Cable Check	8.4.3.2.2	c.1107	PICS_CCK	
15	Pre Charging	8.4.3.3.2	c.1108	PICS_PCH	
16	Current Demand	8.4.3.4.2	c.1109	PICS_CD	
17	Welding detection	8.4.3.5.2	c.1110	PICS_WD	

c.1101: IF PICS_VAS OR PICS_CU OR PICS_CI THEN m ELSE n/a

c.1102: IF PICS_PnC THEN m ELSE n/a

c.1103: IF PICS_CU THEN m ELSE n/a

c.1104: IF PICS_CI THEN m ELSE n/a

c.1105: IF PICS_AC THEN m ELSE n/a

c.1106: IF PICS_AC and PICS_PnC THEN m ELSE n/a

c.1107: IF PICS_DC THEN m ELSE n/a

c.1108: IF PICS_DC THEN m ELSE n/a

c.1109: IF PICS_DC THEN m ELSE n/a

c.1110: IF PICS_DC THEN m ELSE n/a

ANNEX B: TEST PURPOSES FOR EVCC

This annex shows the complete list of test purposes developed for the EVCC.

Page 47	of 172
---------	--------

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.1 SECC discovery

TP Id	TP/EVCC/SDP/CLI/BV/01		
Test objective	Check that the IUT starts the discovery process when IP address is		
	assigned.		
Reference	ISO/IEC 15118-2, 7.10.1.4		
Reference	[V2G2-140],[V2G2-141], [V2G2-142], [V2G2-622], [V2G2-623], [V2G2-018]		
requirement			
Config Id	CF01		
PICS Selection			
Initial conditions			
with{			
the IUT hav	the IUT having assigned an IP address		
}			
Expected behaviour			
ensure that {			
the IUT sends a valid SECC Discovery Request			
}			

TP Id	TP/EVCC/SDP/CLI/BV/02				
Test objective	Checks SECC Discovery Request retransmissions interval				
Reference	ISO/IEC 15118-2, 7.10.1.6				
Reference	[V2G2-159], [V2G2-160]				
requirement					
Config Id	CF01				
PICS Selection					
	Initial conditions				
the IUT ha	with { the IUT having assigned an IP address and the IUT having sent a valid SECC Discovery Request }				
	Expected behaviour				
ensure that {					
}	after 250 ms				

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/SDP/CLI/BV/03
Test objective	Check the SECC Discovery Request maximum number of
	retransmissions
Reference	ISO/IEC 15118-2, 7.10.1.6
Reference	[V2G2-160], [V2G2-161]
requirement	
Config Id	CF01
PICS Selection	
	Initial conditions
with {	
	ving assigned an IP address and
the IUT ha	ving sent a valid SECC Discovery Request
}	
	Expected behaviour
ensure that {	
when {	
	e IUT does not receive a valid SECC Discovery Response
}	
then {	
	e IUT retransmits a valid SECC Discovery Request 4 times
}	
}	

TP Id	TP/EVCC/SDP/CLI/BV/04			
Test objective	Check SECC Discovery Request security encoding validity with TLS			
	selected			
Reference	ISO/IEC 15118-2, 7.10.1.6			
Reference	[V2G2-623]			
requirement				
Config Id	CF01			
PICS Selection	PICS_TLS			
	Initial conditions			
with {				
the IUT hav	ving assigned an IP address and			
the IUT sup	the IUT supporting TLS and intending to use it			
}	}			
	Expected behaviour			
ensure that {	ensure that {			
the	the IUT sends a valid SECC Discovery Request			
	containing Security Encoding field indicating value "0x00"			
	containing Transport Protocol field indicating value "0x00"			
}				

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/SDP/CLI/BV/05	
Test objective	TF/EVCC/3DF/CEI/DV/03	
lest objective	Check SECC Discovery Request security encoding validity with TLS	
	not selected	
	Hot Selected	
Reference	ISO/IEC 15118-2, 7.10.1.6	
Reference	[V2G2-623]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ving assigned an IP address and	
the IUT not	supporting TLS or not intending to use it	
}		
	Expected behaviour	
ensure that {		
the IUT sends a valid SECC Discovery Request		
containing Security Encoding field indicating value "0x10"		
	containing Transport Protocol field indicating value "0x00"	
}		

TP Id	TP/EVCC/SDP/CLI/BO/01	
Test objective	Check that the IUT does not reply to SECC Discovery Request	
Reference	ISO/IEC 15118-2, 7.10.1.5	
Reference	[V2G2-145]	
requirement		
Config Id	CF03	
PICS Selection		
	Initial conditions	
the IUT having assigned an IP address and the IUT having sent a valid SECC Discovery Request and the IUT not having received a valid SECC Discovery Response		
	Expected behaviour	
des } then {	EVCCNodeA sends a SECC Discovery Request with the IUT UDP stination port IUT does not reply the received SECC Discovery Request	
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
-		Contract N. 285285

B.2 Application layer messages

B.2.1. Handshake Protocol

```
TP Id
                   TP/EVCC/ALM/HP/BV/01
 Test objective
                   Checks SupportedApp Request message is sent after receiving SECC
                   Discovery Response message
                   ISO/IEC 15118-DIS-2, section 8.2.1, 8.2.2, 8.4.2
   Reference
                   [V2G2-165], [V2G2-166], [V2G2-167], [V2G2-175], [V2G2-178], [V2G2-483]
    Reference
  requirement
   Config Id
                   CF01
PICS Selection
                                 Initial conditions
with {
       the IUT having sent SECC Discovery Request message
                               Expected behaviour
ensure that {
           when {
                 the IUT receives the SECC Discovery Response message
           then {
                 the IUT sends a SupportedApp Request message
                    containing at least a charging protocol element
                       containing ProtocolNamespace
                       containing VersionNumberMajor
                       containing VersionNumberMinor
                       containing SchemaID
                       containing Priority
                    before V2G_EVCC_Sequence_Performance_Time expires
           }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/HP/BV/02	
Test objective	Check that the IUT does not initiate a session if a SupportedApp	
	Response message contains a 'Failed_NoNegotiation' Response Code	
Reference	ISO/IEC 15118-DIS-2 section 8.2.2	
Reference	[V2G2-173], [V2G2-175], [V2G2-178], [V2G2-484]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ing sent SupportedApp Request message	
}		
	Expected behaviour	
ensure that {		
when {		
the IUT rec	eives a SupportedApp Response	
conta	ining Response Code field	
indicating value 'Failed NoNegotiation'.		
}		
then {		
the IUT does not initiate a session		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.2 Session Setup

```
TP Id
                    TP/EVCC/ALM/SSE/BV/01
  Test objective
                    Check that Session Setup Request message is sent after receiving
                    SupportedAppProtocol Response message
    Reference
                    ISO/IEC 15118-DIS-2, section 8.4.1.2.1, 8.4.1.2.2, 8.8.4.2.1,
    Reference
                    [V2G2-184], [V2G2-186], [V2G2-188]. [V2G2-189], [V2G2-485]
  requirement
    Config Id
                    CF01
 PICS Selection
                                   Initial conditions
with {
       the IUT having sent SupportedAppProtocol Request message
                                  Expected behaviour
ensure that {
            when {
                  the IUT receives the SupportedAppProtocol Response message
                       containing ResponseCode field indicating value
                       'OK_SuccessfullNegotiation'
            \label{eq:then} \} then \{
                  the IUT sends a Session Setup Request message
                     containing a valid Header
                     containing a Body
                        containing EVCCID field
                     before V2G_EVCC_Sequence_Performance_Time expires
            }}
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SSE/BV/02	
Test objective	Check that the IUT closes session if a Session Setup Response	
	message containing a 'FAILED' type Response Code	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.4.2.1. 8.8.3.1	
Reference	[V2G2-486],	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ing sent Session Setup Request message	
}		
	Expected behaviour	
ensure that {		
when {		
the IUT rec	eives a Session Setup Response	
containing Response Code field indicating value `FAILED'.		
}		
then {		
the IUT stops the V2G Communication Session		
\		
\ \ \		
<u> </u>		

TP Id	TP/EVCC/ALM/SSE/BV/03	
Test objective	Checks that the IUT closes session if a Session Setup Response	
	message containing a 'FAILED_SequenceError' type Response Code is	
	received	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.4.2.1. 8.8.3.1	
Reference	[[V2G2-486]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ring sent Session Setup Request message	
}		
	Expected behaviour	
ensure that {		
when {		
the IUT rec	eives a Session Setup Response	
containing Response Code field indicating value 'FAILED_SequenceError'.		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

TP Id	TP/EVCC/ALM/SSE/BV/04		
Test objective	Check that the IUT closes session if a Session Setup Response		
	message containing a 'FAILED_SignatureError' type Response Code is		
	received		
Reference	ISO/IEC 15118-DIS-2 Section 8.8.4.2.1. 8.8.3.1		
Reference	[V2G2-486]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Session Setup Request message		
}	}		
Expected behaviour			
ensure that {			
when {			
the IUT rec	eives a Session Setup Response		
conta	ining Response Code field indicating value `FAILED_SignatureError'.		
_ }			
then {			
the IUT sends a Session Stop Request message			
}			
}			

B.2.3 Service Discovery

```
TP Id
                    TP/EVCC/ALM/SDI/BV/01
  Test objective
                    Check that Service Discovery Request message is sent after
                    receiving Session Setup Response message
                    ISO/IEC 15118-DIS-2, Section 8.4.1.3.2, 8.8.4.2.1 [V2G2-193], [V2G2-194], [V2G2-487]
    Reference
    Reference
  requirement
    Config Id
                    CF01
 PICS Selection
                                    Initial conditions
with {
       the IUT having sent Session Setup Request message
                                   Expected behaviour
ensure that {
            when {
                  the IUT receives the Session Setup Response message
                     containing ResponseCode field indicating value 'OK'
            then {
                  the IUT sends a Service Discovery Request message
                     containing a valid Header
                     containing a Body
                     before V2G_EVCC_Sequence_Perfomance_Time expires
            }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SDI/BV/02		
Test objective	Check that the IUT stops session if a Service Discovery Response		
	message containing a 'FAILED' -type Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-488]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Service Discovery Request message		
}			
Expected behaviour			
ensure that {			
when {			
the IUT rec	eives a Service Discovery Response message		
containing Response Code field indicating value 'FAILED'			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

TP Id	TP/EVCC/ALM/SDI/BV/03	
Test objective	Check that the IUT stops session if a Service Discovery Response	
	message containing a `FAILED_SequenceError' -type Response Code	
	is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-488]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ing sent Service Discovery Request message	
}		
Expected behaviour		
ensure that {		
when {		
the IUT rec	eives a Service Discovery Response message	
containing Response Code field indicating value `FAILED_SequenceError'		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SDI/BV/04		
Test objective	Check that the IUT stops session if a Service Discovery Response		
	message containing a 'FAILED_SignatureError' -type Response Code		
	is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-488]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Service Discovery Request message		
}			
Expected behaviour			
ensure that {			
when {			
the IUT rec	eives a Service Discovery Response message		
conta	ining Response Code field indicating value 'FAILED SignatureError'		
}			
then {			
the IUT stops the V2G Communication Session			
}			
} `	· · · · · · · · · · · · · · · · · · ·		

TP Id	TP/EVCC/ALM/SDI/BV/05		
Test objective	Check that the IUT stops session if a Service Discovery Response		
	message containing a 'FAILED_UnknownSession' -type Response		
	Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-488]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Service Discovery Request message		
}			
Expected behaviour			
ensure that {			
when {	when {		
	eives a Service Discovery Response message		
conta	ining Response Code field indicating value `FAILED_UnknownSession'		
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

B.2.4 Service Details

```
TP Id
                    TP/EVCC/ALM/SDE/BV/01
  Test objective
                    Check that Service Details Request message is sent after receiving
                    Service Discovery Response message offering a Service List
                    ISO/IEC 15118-DIS-2, Section 8.4.1.4.1, 8.8.4.2.1 [V2G2-197], [V2G2-198], [V2G2-489]
    Reference
    Reference
  requirement
    Config Id
                    CF01
 PICS Selection
                    PICS_SDE and (PICS_VAS or PICS_CI or PICS_CU)
                                    Initial conditions
with {
       the IUT having sent Service Discovery Request message
                                   Expected behaviour
ensure that {
            when {
                  the IUT receives the Service Discovery Response message
                     containing ResponseCode field indicating value 'OK'
                      containing ServiceList field
            then {
                  the IUT sends a Service Details Request message
                      containing a valid Header
                      containing a Body
                        containing ServiceID field
                      before V2G_EVCC_Sequence_Perfomance_Time expires
            }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SDE/BV/02	
Test objective		
Service Detail Response message when further detailed infor		
	is required	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.4.1, 8.8.4.2.1	
Reference	[V2G2-197], [V2G2-198], [V2G2-494]	
requirement		
Config Id	CF01	
PICS Selection	PICS_SDE and (PICS_VAS or PICS_CI or PICS_CU)	
	Initial conditions	
with {		
the IUT hav	ing sent Service Details Request message	
}		
	Expected behaviour	
ensure that {		
when -	•	
1	the IUT receives the Service Details Response message	
	containing ResponseCode field indicating value 'OK'	
}		
then {		
1	the IUT sends a Service Details Request message	
	containing a valid Header	
	containing a Body	
	containing ServiceID field	
1	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
J		

TP Id	TP/EVCC/ALM/SDE/BV/03		
Test objective	Check that the IUT stops session if a Service Detail Response		
	message containing a 'FAILED'-type Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-491]		
requirement			
Config Id	CF01		
PICS Selection	PICS_SDE and (PICS_VAS or PICS_CI or PICS_CU)		
	Initial conditions		
with {			
the IUT hav	the IUT having sent Service Detail Request message		
}			
	Expected behaviour		
ensure that {			
when {			
	the IUT receives a Service Detail Response message		
containing Response Code field indicating value `FAILED '			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SDE/BV/04	
Test objective	Check that the IUT stops session if a Service Detail Response	
	message containing a 'FAILED_SequenceError'-type Response Code is	
	received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-491]	
requirement		
Config Id	CF01	
PICS Selection	PICS_SDE and (PICS_VAS or PICS_CI or PICS_CU)	
	Initial conditions	
with {		
the IUT hav	ing sent Service Detail Request message	
}		
Expected behaviour		
ensure that {		
when {		
the IUT rec	eives a Service Detail Response message	
containing Response Code field indicating value `FAILED_SequenceError'		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

TP Id	TP/EVCC/ALM/SDE/BV/05	
Test objective	Check that the IUT stops session if a Service Detail Response	
rest objective	message containing a 'FAILED_SignatureError'-type Response Code is	
	received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-491]	
requirement		
Config Id	CF01	
PICS Selection	PICS_SDE and (PICS_VAS or PICS_CI or PICS_CU)	
	Initial conditions	
with {		
the IUT hav	ing sent Service Detail Request message	
}		
	Expected behaviour	
ensure that {		
when {		
	eives a Service Detail Response message	
containing Response Code field indicating value `FAILED_SignatureError'		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SDE/BV/06		
Test objective	Check that the IUT stops session if a Service Detail Response		
	message containing a `FAILED_UnknownSession'-type Response Code		
	is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-491]		
requirement			
Config Id	CF01		
PICS Selection	PICS_SDE and (PICS_VAS or PICS_CI or PICS_CU)		
	Initial conditions		
with {			
the IUT hav	the IUT having sent Service Detail Request message		
}			
	Expected behaviour		
ensure that {			
when {			
the IUT rec	eives a Service Detail Response message		
containing Response Code field indicating value 'FAILED_ UnknownSession'			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

TP Id	TP/EVCC/ALM/SDE/BV/07		
Test objective	Check that the IUT stops session if a Service Detail Response message containing a 'FAILED_ServiceIDInvalid' -type Response Code		
	is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-491]		
requirement			
Config Id	CF01		
PICS Selection	PICS_SDE and (PICS_VAS or PICS_CI or PICS_CU)		
	Initial conditions		
with {			
the IUT hav	ing sent Service Detail Request message		
}			
	Expected behaviour		
ensure that {			
	when {		
	eives a Service Detail Response message		
containing Response Code field indicating value `FAILED_ServiceIDInvalid'			
}			
then {			
the IUT stops the V2G Communication Session			
}			
了			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
-		Contract N. 285285

B.2.5 Service and Payment Selection

TP Id	TP/EVCC/ALM/SPS/BV/01
Test objective Checks Service and Payment Selection Request message is se	
after receiving Service Details Response message in PnC	
	identification mode
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.5.2, 8.6.3.6, 8.8.4.2.1, 8.6.3.2
Reference	[V2G2-201], [V2G2-202], [V2G2-431], [V2G2-432], [V2G2-493], [V2G2-404]
requirement	
Config Id	CF01
PICS Selection	PICS_SDE and PICS_PnC
	Initial conditions
with {	
the IUT hav	ring sent Service Details Request message
}	
	Expected behaviour
ensure that {	
when {	
t	the IUT receives the Service Details Response message
	containing ResponseCode field indicating value 'OK'
}	
then {	
t	the IUT sends a Service and Payment selection Request message
	containing a valid Header
	containing a Body
	containing Selected ServiceList
	containing ServiceID field
	containing Selected PaymentOption field
	indicating value `contract'
	before V2G_EVCC_Sequence_Perfomance_Time expires
}	
_ }	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TDI	TRIFLICCIAL MICRO IRVING	
TP Id	TP/EVCC/ALM/SPS/BV/02	
Test objective	Checks Service and Payment Selection Request message is sent	
	after receiving Service Details Response message in EIM	
	identification mode	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.5.2, 8.6.3.6, 8.8.4.2.1, 8.6.3.2	
Reference	[V2G2-201], [V2G2-202], [V2G2-431], [V2G2-432], [V2G2-493], [V2G2-402],	
requirement	[V2G2-403]	
Config Id	CF01	
PICS Selection	PICS SDE and PICS EIM	
	Initial conditions	
with {		
	ving sent Service Details Request message	
}	5	
	Expected behaviour	
ensure that {		
when	(
	the IUT receives the Service Details Response message	
· ·	containing ResponseCode field indicating value 'OK'	
}	containing responsecode near indicating value or	
then {		
1	the IUT sends a Service and Payment selection Request message	
	containing a valid Header	
	containing a Body	
	containing Selected ServiceList field	
	containing ServiceID field	
	containing Selected PaymentOption field	
indicating value `External Payment'		
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		
` '		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SPS/BV/03		
Test objective Check that Service and Payment Selection Request message is			
	after receiving Service Discovery Response message in PnC		
	identification mode		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.5.2, 8.6.3.6, 8.8.4.2.1, 8.6.3.2		
Reference	V2G2-201], [V2G2-202], [V2G2-431], [V2G2-432], [V2G2-490], [V2G2-404]		
requirement			
Config Id	CF01		
PICS Selection	PICS_PnC		
	Initial conditions		
with {			
the IUT hav	ring sent Service Discovery Request message		
}			
	Expected behaviour		
ensure that {			
when {			
į t	the IUT receives the Service Discovery Response message		
_	containing ResponseCode field indicating value 'OK'		
}			
then {			
	the IUT sends a Service and Payment selection Request message		
	containing a valid Header		
	containing a Body		
	containing Selected ServiceList field		
	containing Selected PaymentOption field		
	indicating value 'contract'		
	before V2G_EVCC_Sequence_Perfomance_Time expires		
}			
<u> </u>			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

	,		
TP Id	TP/EVCC/ALM/SPS/BV/04		
Test objective	Check that Service and Payment Selection Request message is sent		
	after receiving Service Discovery Response message in EIM		
	identification mode		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.5.2, 8.6.3.6, 8.8.4.2.1, 8.6.3.2		
Reference	V2G2-201], [V2G2-202], [V2G2-431], [V2G2-432], [V2G2-490], [V2G2-402],		
requirement	[V2G2-403],		
Config Id	CF01		
PICS Selection	PICS_EIM		
	Initial conditions		
with {			
the IUT hav	ving sent Service Discovery Request message		
}			
	Expected behaviour		
ensure that {			
when -			
1	the IUT receives the Service Discovery Response message		
	containing ResponseCode field indicating value 'OK'		
}			
then {			
1	the IUT sends a Service and Payment selection Request message		
	containing a valid Header		
	containing a Body		
containing Selected ServiceList field			
	containing Selected PaymentOption field		
	indicating value 'External Payment'		
	before V2G_EVCC_Sequence_Perfomance_Time expires		
}			
}			

TP Id	TP/EVCC/ALM/SPS/BV/05		
Test objective	Check that the IUT stops session if a Service and Payment Selection		
	Response message containing a 'FAILED'-type Response Code is		
	received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-492]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	the IUT having sent Service and Payment Selection Request message		
}			
	Expected behaviour		
ensure that {			
when {			
the IUT rec	eives a Service and Payment Selection Response message		
containing Response Code field indicating value 'FAILED'			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

	<u> </u>	
TP Id	TP/EVCC/ALM/SPS/BV/06	
Test objective	Check that the IUT stops session if a Service and Payment Selection	
	Response message containing a `FAILED_SequenceError'-type	
	Response Code is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-492]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ing sent Service and Payment Selection Request message	
}		
Expected behaviour		
ensure that {		
when {		
the IUT rec	eives a Service and Payment Selection Response message	
conta	ining Response Code field indicating value 'FAILED_SequenceError'	
}		
then {		
the IUT sends a Session Stop Request message		
}		
}		

TP/EVCC/ALM/SPS/BV/07		
Check that the IUT stops session if a Service and Payment Selection		
Response message containing a `FAILED_SignatureError'-type		
Response Code is received		
ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
[V2G2-492]		
CF01		
Initial conditions		
ing sent Service and Payment Selection Request message		
}		
Expected behaviour		
ensure that {		
eives a Service and Payment Selection Response message		
containing Response Code field indicating value 'FAILED_SignatureError'		
}		
then {		
the IUT stops the V2G Communication Session		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SPS/BV/08		
Test objective	Check that the IUT stops session if a Service and Payment Selection		
	Response message containing a `FAILED_UnknownSession'-type		
	Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-492]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Service and Payment Selection Request message		
}	}		
	Expected behaviour		
ensure that {			
when {			
the IUT rec	eives a Service and Payment Selection Response message		
	ining Response Code field indicating value 'FAILED_ UnknownSession'		
}			
then {			
the IUT stops the V2G Communication Session			
}			
} `			

TP Id	TP/EVCC/ALM/SPS/BV/09		
Test objective	Check that the IUT stops session if a Service and Payment Selection		
	Response message containing a `FAILED_ServiceSelectionInvalid'-		
	type Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-492]		
requirement			
Config Id	CF01		
PICS Selection			
Initial conditions			
with {			
the IUT hav	ing sent Service and Payment Selection Request message		
}			
Expected behaviour			
ensure that {			
when {			
	eives a Service and Payment Selection Response message		
containing Response Code field indicating value			
`FAILED_ServiceSelectionInvalid'.			
}			
then {			
the IUT stops the V2G Communication Session			
}	}		
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SPS/BV/10	
Test objective	Check that the IUT stops session if a Service and Payment Selection	
	Response message containing a `FAILED_PaymentSelectionInvalid'-	
	type Response Code is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-492]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ing sent Service and Payment Selection Request message	
}		
Expected behaviour		
ensure that {		
when {		
the IUT rec	eives a Service and Payment Selection Response message	
conta	ining Response Code field indicating value 'FAILED_PaymentSelection	
Invalid'.		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.6 Certificate Update

```
TP Id
                  TP/EVCC/ALM/CU/BV/01
                  Check that Certificate update Request message is sent after receiving
 Test objective
                  Service and Payment Selection Response message containing
                  Response Code indicating value 'OK'
   Reference
                  ISO/IEC 15118-DIS-2, Section 8.4.1.10.2, 8.8.4.2.1
   Reference
                  [V2G2-228], [V2G2-229], [V2G2-497]
  requirement
   Config Id
                  CF01
 PICS Selection
                  PICS_CU and PICS_PnC
                                   Initial conditions
with {
               the IUT having sent Service and Payment Request message
                       containing SelectedServiceList
                              containing SelectedService field
                                      containing Service ID field indicating value ' 2'
(Certificate Update/install)
                                  Expected behaviour
ensure that {
            when {
                  the IUT receives the Service and Payment Selection Response
message
                  containing ResponseCode field indicating value 'OK'
            then {
                  the IUT sends a Certificate update Request message
                     containing a valid Header
                     containing a Body
                       containing Contract_id
                       containing ChallengeSignature
                       containing ListOfRootCertificateIDs
                       containing RootCertificateID
            before V2G_EVCC_Sequence_Perfomance_Time expires
            }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CU/BV/02		
Test objective	Check that the IUT closes session if a Certificate Update Response		
	message containing a 'FAILED'-type Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-555]		
requirement			
Config Id	CF01		
PICS Selection	PICS_CU and PICS_PnC		
	Initial conditions		
with {			
the IUT hav	ing sent Certificate Update Request message		
}			
Expected behaviour			
ensure that {			
when {	when {		
the IUT receives a Certificate Update Response mesage			
conta	ining Response Code field indicating value 'FAILED'		
}			
then {			
the IUT stops the V2G Communication Session			
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \			
}			

TP Id	TD/EV/CC/ALM/CH/DV/O2		
	TP/EVCC/ALM/CU/BV/03		
Test objective	Check that the IUT closes session if a Certificate Update Response		
	message containing a 'FAILED_CertChainError' -type Response Code		
	is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-555]		
requirement			
Config Id	CF01		
PICS Selection	PICS_CU and PICS_PnC		
	Initial conditions		
with {			
7	ing sent Certificate Update Request message		
}			
Expected behaviour			
ensure that {			
when {			
the IUT rec	the IUT receives a Certificate Update Response message		
	containing Response Code field indicating value 'FAILED CertChainError'		
}			
then {			
the IUT stops the V2G Communication Session			
the 101 stops the 420 communication session			
\			
\ \			
J			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id TP/EVCC/ALM/CU/BV/04 Test objective Check that the IUT closes session if a Certificate		
Test objective Check that the IUT closes session if a Certificate		
rest objective check that the 101 closes session if a certificate	e Update Response	
message containing a `FAILED_NoCertificateAva	ilable' -type Response	
Code is received		
Reference ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference [V2G2-555]		
requirement		
Config Id CF01		
PICS Selection PICS_CU and PICS_PnC		
Initial conditions		
with {		
the IUT having sent Certificate Update Request message		
}		
Expected behaviour		
ensure that {		
when {		
the IUT receives a Certificate Update Response message		
containing Response Code field indicating value		
`FAILED NoCertificateAvailable'		
then {		
the IUT stops the V2G Communication Session		
}		
}		

TP Id	TP/EVCC/ALM/CU/BV/05	
Test objective	Check that the IUT closes session if a Certificate Update Response	
	message containing a 'FAILED_ContractCanceled' -type Response	
	Code is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-555]	
requirement		
Config Id	CF01	
PICS Selection	PICS_CU and PICS_PnC	
	Initial conditions	
with {		
the IUT having sent Certificate Update Request message		
}		
Expected behaviour		
ensure that {		
when {		
the IUT receives a Certificate Update Response message		
containing Response Code field indicating value 'FAILED_ContractCanceled'		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CU/BV/06	
Test objective	Check that the IUT closes session if a Certificate Update Response	
	message containing a `FAILED_CertificateExpired' -type Response	
	Code is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-555]	
requirement		
Config Id	CF01	
PICS Selection	PICS_CU and PICS_PnC	
Initial conditions		
with {		
the IUT hav	ing sent Certificate Update Request message	
}		
Expected behaviour		
ensure that {		
when {		
the IUT receives a Certificate Update Response message		
containing Response Code field indicating value		
'FAILED CertificateExpired'		
}		
then {		
the IUT stops the Communication Session		
the for stops the communication session		
}		
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		

B.2.7 Certificate Installation

```
TP Id
                   TP/EVCC/ALM/CI/BV/01
                   Check that Certificate Install Request message is sent after receiving
 Test objective
                  Service and Payment Selection Response message containing
                  Response Code indicating value 'OK'
                  ISO/IEC 15118-DIS-2, Section 8.4.1.11.2, 8.8.4.2.1
   Reference
                  [V2G2-235], [V2G2-236], [V2G2-496]
   Reference
  requirement
                  CF01
   Config Id
                  PICS_CI and PICS_PnC
 PICS Selection
                                   Initial conditions
with {
       the IUT having sent Service and Payment Request message
               containing SelectedServiceList
                       containing SelectedService field
                               containing Service ID field indicating value ' 2'
(Certificate Update/install)
                                  Expected behaviour
ensure that {
            when {
                  the IUT receives the Service and Payment selection Res message
                  containing ResponseCode field indicating value 'OK'
            then {
                  the IUT sends a Certificate install Request message
                     containing a valid Header
                     containing a Body
```

```
containing OEMProvisioningCert
containing ListOfRootCertificateIDs
before V2G_EVCC_Sequence_Perfomance_Time expires
}
}
```

TP Id	TP/EVCC/ALM/CI/BV/02	
Test objective	Check that the IUT stops session if a Certificate Install Response	
	message containing a 'FAILED' Response Code is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-498]	
requirement		
Config Id	CF01	
PICS Selection	PICS_CI and PICS_PnC	
	Initial conditions	
with {		
the IUT hav	ing sent Certificate Install Request message	
}		
Expected behaviour		
ensure that {		
when {		
	eives a Certificate Install Response message	
containing Response Code field indicating value 'FAILED'		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CI/BV/03	
Test objective	Check that the IUT closes session if a Certificate Install Response	
	message containing a 'FAILED_NoCertificateAvailable' Response Code	
	is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-498]	
requirement		
Config Id	CF01	
PICS Selection	PICS_CI and PICS_PnC	
	Initial conditions	
with {		
the IUT hav	ing sent Certificate Install Request message	
}		
	Expected behaviour	
ensure that {		
when {		
	eives a Certificate Install Response message	
	ntaining Response Code field indicating value	
`FAILED_NoCertificateAvailable'		
}		
then {		
the IUT stop	the IUT stops the V2G Communication Session	
}		
}		

TP Id	TP/EVCC/ALM/CI/BV/04		
Test objective	Check that the IUT closes session if a Certificate Install Response		
	message containing a `FAILED_CertificateExpired' Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-498]		
requirement			
Config Id	CF01		
PICS Selection	PICS_CI and PICS_PnC		
	Initial conditions		
with {			
the IUT hav	ing sent Certificate Install Request message		
}			
	Expected behaviour		
ensure that {			
when {			
the IUT receives a Certificate Install Response message			
	ntaining Response Code field indicating value		
_	`FAILED_CertificateExpired'		
}			
then {			
the IUT stop	os the V2G Communication Session		
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \			
}			

B.2.8 Payment Details

Page 74 of 172
1 age 7 1 01 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

```
TP Id
                    TP/EVCC/ALM/PDT/BV/01
                    Check that Payment Details Request message is sent after receiving
  Test objective
                    Service and Payment Selection Response message
                    ISO/IEC 15118-DIS-2, Section 8.4.1.6.2, 8.8.4.2.1 [V2G2-205], [V2G2-206], [V2G2-495]
    Reference
    Reference
  requirement
                    CF01
    Config Id
 PICS Selection
                    PICS PDT and PICS PnC
                                    Initial conditions
with {
        the IUT having sent Service and Payment selection Request message
                containing PaymentOption indicating value 'contract'
                                   Expected behaviour
ensure that {
         when {
               the IUT receives the Service and Payment Selection Response message
                  containing ResponseCode field indicating value 'OK'
         then {
               the IUT sends a Payment Details Request message
                  containing a valid Header
                  containing a Body
                     containing ContractID field
                     containing ContractSignatureCertChain field
                         containing Certificate
                         containing SubCertificates
                         containing Certificate
               before V2G_EVCC_Sequence_Perfomance_Time expires
         }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PDT/BV/02		
Test objective	Check that Payment Details Request message is sent after receiving		
	Certificate Installation Response message		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.6.2, 8.8.4.2.1		
Reference	[V2G2-205], [V2G2-206], [V2G2-500]		
requirement			
Config Id	CF01		
PICS Selection	PICS_PDT and PICS_CI and PICS_PnC		
	Initial conditions		
with {			
the IUT hav	ring sent Certificate Installation Request message		
}			
	Expected behaviour		
ensure that {			
when {			
	IUT receives the Certificate installation Response message		
	containing ResponseCode field indicating value 'OK'		
}			
then {			
	IUT sends a Payment Details Request message		
	containing a valid Header		
•	containing a Body		
	containing ContractID field		
	containing ContractSignatureCertChain field		
containing Certificate			
containing SubCertificates			
has	containing Certificate		
	ore V2G_EVCC_Sequence_Perfomance_Time expires		
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TD/EV/CC/ALM/DDT/DV/03	
	TP/EVCC/ALM/PDT/BV/03	
Test objective	Check that Payment Details Request message is sent after receiving	
	Certificate Update Response message	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.6.2, 8.8.4.2.1	
Reference	[V2G2-205], [V2G2-206], [V2G2-501]	
requirement		
Config Id	CF01	
PICS Selection	PICS_PDT and PICS_CU and PICS_PnC	
	Initial conditions	
with {		
the IUT hav	ring sent Certificate Update Request message	
}		
	Expected behaviour	
ensure that {	•	
when {		
	the IUT receives the Certificate Update Res message	
	containing ResponseCode field indicating value 'OK'	
}		
then {		
_	the IUT sends a Payment Details Request message	
	containing a valid Header	
	containing a Body	
	containing ContractID field	
	containing ContractSignatureCertChain field	
	containing ContractsignatureCertChair heid	
	containing Certificates	
	_	
	containing Certificate	
1	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
<u> </u>		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PDT/BV/04		
Test objective	Check that the IUT stops session if a Payment Details Response		
	message containing a 'FAILED' Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-502]		
requirement			
Config Id	CF01		
PICS Selection	PICS_PDT and PICS_PnC		
	Initial conditions		
with {			
the IUT hav	ing sent Payment Details Request message		
}	}		
	Expected behaviour		
ensure that {	·		
when {			
the IUT receives a Payment Details Response message			
	ining Response Code field indicating value 'FAILED'		
}			
then {			
the IUT stops the V2G Communication Session			
}			
} `			
J			

TP Id	TP/EVCC/ALM/PDT/BV/05		
Test objective	Check that the IUT stops session if a Payment Details Response		
	message containing a 'FAILED_CertificateExpired'-type Response		
	Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-502]		
requirement			
Config Id	CF01		
PICS Selection	PICS_PDT and PICS_PnC		
	Initial conditions		
with {			
the IUT having sent Payment Details Request message			
}			
Expected behaviour			
ensure that {			
when {	when {		
the IUT rec	the IUT receives a Payment Details Response message		
containing Response Code field indicating value `FAILED_CertificateExpired'.			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.9 Contract Authentication

TP Id	TP/EVCC/ALM/CA/BV/01	
Test objective	Check that Contract Authentication Request message is sent after	
	receiving Payment Details Response message	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.7.1, 8.8.4.2.1	
Reference	[V2G2-210], [V2G2-211], [V2G2-503]	
requirement		
Config Id	CF01	
PICS Selection	PICS_PDT and PICS_PnC	
	Initial conditions	
with {		
the IUT hav	ring sent Payment Details Request message	
}		
	Expected behaviour	
ensure that {		
when -		
	the IUT receives the Payment Details Response message	
	containing ResponseCode field indicating value 'OK'	
}		
then {		
the IUT sends a Contract Authentication Request message		
	containing a valid Header	
	containing a Body	
	containing ID field	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TD 14	TD/EVCC/ALM/CA/DV/O2	
TP Id	TP/EVCC/ALM/CA/BV/02	
Test objective	Check that Contract Authentication Request message is sent after	
	receiving Service and Payment Selection Response message	
	(External payment case)	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.7.1, 8.8.4.2.1	
Reference	[V2G2-210], [V2G2-211], [V2G2-509]	
requirement		
Config Id	CF01	
PICS Selection	PICS EIM	
	Initial conditions	
with {		
-	ving sent Service and Payment Request message	
con	staining SelectedPaymentOption field indicating value 'External	
Payment'	3 , 1	
}		
	Expected behaviour	
ensure that {		
when -		
	the IUT receives the Service and Payment selection message	
· ·	containing ResponseCode field indicating value 'OK'	
3	containing responsessae held indicating value or	
then {		
the IUT sends a Contract Authentication Request message		
	containing a valid Header	
	containing a Body	
	containing ID field	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CA/BV/03	
Test objective		
	receiving Contract Authentication Response message when the	
	parameter EVSEProcessing is equal to 'Ongoing'	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.7.1, 8.8.4.2.1	
Reference	[V2G2-210], [V2G2-211], [V2G2-684]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ring sent Contract Authentication Request message	
}		
	Expected behaviour	
ensure that {		
when {		
t	the IUT receives the Contract Authentication Resoponse message	
	containing ResponseCode field indicating value 'OK'	
	containing EVSEProcessing field indicating value 'Ongoing'	
}		
then {		
1	the IUT sends a Contract Authentication Request message	
	containing a valid Header	
	containing a Body	
	containing ID field	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

TP Id	TP/EVCC/ALM/CA/BV/04		
Test objective Check that the IUT stops session if a Contract Authentication			
	Response message containing a `FAILED_ChallengeInvalid' Response		
	Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-504]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ring sent Contract Authentication Request message		
}			
	Expected behaviour		
ensure that {			
when {			
t	the IUT receives a Contract Authentication Response message		
	containing ResponseCode field indicating value		
	`FAILED_ChallengeInvalid'		
}			
then {			
t	the IUT stops the V2G Communication Session		
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CA/BV/05	
Test objective	Check that the IUT stops session if a Contract Authentication	
	Response message containing a 'FAILED' Response Code is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1	
Reference	[V2G2-504]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
-	ing sent Contract Authentication Request message	
}		
Expected behaviour		
ensure that {		
when {		
the IUT rec	eives a Contract Authentication Response message	
containing Response Code field indicating value 'FAILED'		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		
-		

TP Id	TP/EVCC/ALM/CA/BV/06		
Test objective	Check that the IUT stops session if a Contract Authentication		
	Response message containing a `FAILED_SequenceError' Response		
	Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-504]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Contract Authentication Request message		
}			
Expected behaviour			
ensure that {			
when {			
the IUT rec	eives a Contract Authentication Response message		
conta	containing Response Code field indicating value `FAILED_SequenceError'		
}			
then {			
the IUT stops the V2G Communication Session			
}	}		
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CA/BV/07		
Test objective	Check that the IUT stops session if a Contract Authentication		
	Response message containing a 'FAILED_SignatureError' Response		
	Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-504]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT having sent Contract Authentication Request message			
}			
Expected behaviour			
ensure that {			
when {			
the IUT rece	eives a Contract Authentication Response message		
containing Response Code field indicating value `FAILED_SignatureError'			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

TP Id	TD/EV/CC/ALM/CA/BV/OS		
	TP/EVCC/ALM/CA/BV/08		
Test objective	Check that the IUT stops session if a Contract Authentication		
	Response message containing a 'FAILED_UnknownSession' Response		
	Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-504]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT having sent Contract Authentication Request message			
}			
	Expected behaviour		
ensure that {			
when {			
-	eives a Contract Authentication Response message		
	ining Response Code field indicating value 'FAILED_UnknownSession'		
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.10 Charge parameter Discovery

TP Id Test objective	TP/EVCC/ALM/CPD/BV/01 Check that Charge Parameter Discovery Request message is sent	
rest objective	check that charge rarameter biscovery request message is sent	
after receiving Contract Authentication Response message with		
	parameter 'EVSEProcessing' set to 'Finished' in AC mode	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.8.2, 8.8.4.2.1	
Reference	[V2G2-214], [V2G2-216], [V2G2-217], [V2G2-505]	
requirement		
Config Id	CF01	
PICS Selection	PICS AC	
	Initial conditions	
with {		
	ring sent Contract Authentication Request message	
}		
	Expected behaviour	
ensure that {		
when {		
t	the IUT receives the Contract Authentication Response message	
	containing ResponseCode field indicating value 'OK'	
	containing EVSEProcessing field indicating value 'Finished'	
}		
then {		
t	the IUT sends a Charge Parameter Discovery Request message	
	containing a valid Header	
	containing a Body	
	containing EVRequestedEnergyType indicating value	
	'AC_three_phase_core' or 'AC _single_phase_core'	
	containing AC_EVChargeParameter type	
	containing Departure time indicating	
	containing EAmount	
	containing Multiplier field	
	containing Value field	
	containing PEVMaxVoltage	
	containing Multiplier field containing Value field	
	containing value held containing PEVMaxCurrent	
	containing Multiplier field	
	containing Multiplier field	
	containing value held containing PEVMinCurrent	
	containing Multiplier field	
	containing Value field	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}	20.0.0 120_2100_00quellec_l'ellomanec_time expires	
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CPD/BV/02	
Test objective	Check that Charge Parameter Discovery Request message is sent	
rest objective	after receiving Contract Authentication Response message with	
	parameter 'EVSEProcessing' set to 'Finished' in DC mode	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.8.2, 8.8.4.2.1	
Reference	[V2G2-214], [V2G2-216], [V2G2-217], [V2G2-505]	
requirement	[], [], [], []	
Config Id	CF01	
PICS Selection	PICS DC	
1 103 Sciection	Initial conditions	
with {	Titled Conditions	
	ring sent Contract Authentication Request message	
}	mig sent contract nathenatation request message	
	Expected behaviour	
ensure that {		
when {		
t	the IUT receives the Contract Authentication Response message	
	containing ResponseCode field indicating value 'OK'	
	containing EVSEProcessing field indicating value 'Finished'	
}		
then {		
t	the IUT sends a Charge Parameter Discovery Request message	
	containing a valid Header	
	containing a Body	
	containing EVRequestedEnergyType indicating value	
	'DC _core' or 'DC_extended' or 'DC_combo_core' or 'DC_unique'	
	containing DC_EVChargeParameter type	
	containing DC_EVStatus	
	containing EVReady	
containing EVErrorCode		
containing EVRESSSOC		
containing EVMaximumCurrentLimit		
containing Multiplier field		
	containing Value field	
	containing EVMaximumVoltageLimit	
	containing Multiplier field	
	containing Value field	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CPD/BV/03		
Test objective	Check that Charge Parameter Discovery Request message is resent		
after receiving Charge Parameter Discovery Response message			
	(EVSEProcessing: ongoing)		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.8.2, 8.8.4.2.1		
Reference	[V2G2-214], [V2G2-216], [V2G2-217], [V2G2-685]		
requirement			
Config Id	CF01		
PICS Selection	PICS_AC		
	Initial conditions		
with {			
	ving sent Charge Parameter Discovery Request message		
}	gg		
,	Expected behaviour		
ensure that {	·		
when -	{		
	the IUT receives the Charge Parameter Discovery Response message		
	containing EVSEProcessing field indicating value 'Ongoing'		
}			
then {			
	the IUT resends a Charge Parameter Discovery Request message		
	containing a valid Header		
	containing a Body		
	containing EVRequestedEnergyType indicating value		
	'AC_three_phase_core' or 'AC _single_phase_core'		
	containing AC_EVChargeParameter type		
	containing Departure time		
	indicating value 'Time in UTC'		
	containing EAmount		
	containing Multiplier field		
	containing Value field		
containing PEVMaxVoltage			
containing Multiplier field			
containing Value field			
containing PEVMaxCurrent			
containing Multiplier field			
containing Value field			
containing PEVMinCurrent			
containing Multiplier field			
	containing Value field		
	before V2G_EVCC_Sequence_Perfomance_Time expires		
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CPD/BV/04		
Test objective	Check that the IUT stops session if a Charge Parameter Discovery		
	Response message containing a 'FAILED' Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.8.3		
Reference	[V2G2-506]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
-	ing sent Charge Parameter Discovery Request message		
}			
Expected behaviour			
ensure that {			
when {			
the IUT rec	eives a Charge Parameter Discovery Response message		
containing Response Code field indicating value 'FAILED'.			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

TP Id	TP/EVCC/ALM/CPD/BV/05		
Test objective	Check that the IUT stops session if a Charge Parameter Discovery		
	Response message containing a `FAILED_WrongEnergyTransferType'		
	Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.8.3		
Reference	[V2G2-506]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Charge Parameter Discovery Request message		
}			
Expected behaviour			
ensure that {			
when {			
	eives a Charge Parameter Discovery Response message		
conta	containing Response Code field indicating		
`FAILED_WrongEnergyTransferType' .			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

	-		
TP Id	TP/EVCC/ALM/CPD/BV/06		
Test objective	Check that the IUT stops session if a Charge Parameter Discovery		
	Response message containing a 'FAILED_WrongChargeParameter'		
	Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.8.3		
Reference	[V2G2-506]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
-	ing sent Charge Parameter Discovery Request message		
}			
Expected behaviour			
ensure that {			
when {			
the IUT rec	eives a Charge Parameter Discovery Response message		
	ining Response Code field indicating value		
	rongChargeParameter'.		
}			
then {			
the IUT stops the V2G Communication Session			
•	35 the V2G Communication Session		
}	}		
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.11 Power Delivery

}			
Expected behaviour			
ensure that {	Expected bendition		
	ſ		
	· · · · · · · · · · · · · · · · · · ·		
	the IUT receives the Charge Parameter Discovery Response message		
	containing ResponseCode field indicating value 'OK'		
	containing EVSEProcessing field indicating value 'Finished'		
1	totag = 1 0 = 1 10 to to the transacting value 1 illioned		
}			
the IUT sends a Power Delivery Request message			
containing a valid Header			
containing a valid Header			
containing a valid Header			
the IUT sends a Power Delivery Request message			
then {			
}			
) ,			
	containing Evoler occasing near indicating value Tillished		
	containing FVSFProcessing field indicating value 'Finished'		
	containing ResponseCode field indicating value 'OK'		
	the IUT receives the Charge Parameter Discovery Response message		
	· · · · · · · · · · · · · · · · · · ·		
when -	{		
ensure that {			
	Expected beliavioui		
	Expected behaviour		
J			
}			
the 101 hav	ving sent Charge Parameter Discovery Request message		
	ving cont Charge Darameter Discovery Request message		
with {			
	Illitial Collutions		
	Initial conditions		
PICS Selection	PICS_AC		
Config Id	CF01		
requirement			
	[4292-221], [4292-222], [4292-310]		
Reference	[V2G2-221], [V2G2-222], [V2G2-510]		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.2, 8.8.4.2.2		
	`EVSEProcessing' set to 'Finished'		
	Charge Parameter Discovery Response message with parameter		
Test objective	Check that Power Delivery Request message is sent after receiving		
TP Id	TP/EVCC/ALM/PWD/BV/01		
TD 1.1	TD/EV/CC/ALM/DM/D/DV/O1		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PWD/BV/02	
Test objective	Check that Power delivery Request message is sent after receiving	
	Charging status Response message	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.2, 8.8.4.2.2	
Reference	[V2G2-221], [V2G2-222], [V2G2-521]	
requirement		
Config Id	CF01	
PICS Selection	PICS_AC	
	Initial conditions	
with {		
the IUT hav	ring sent Charging status Request message	
}		
	Expected behaviour	
ensure that {		
when {		
t	the IUT receives the Charging Status Response message	
	containing Receipt Required field indicating value 'FALSE'	
}		
then {		
	the IUT sends a Power Delivery Request message	
	containing a valid Header	
	containing a Body	
	containing Ready to charge State field indicating value 'FALSE'	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PWD/BV/03	
Test objective	Check that Power delivery Request message is sent after receiving	
	Metering Receipt Response message (stop charging case)	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.2, 8.8.4.2.2	
Reference	[V2G2-221], [V2G2-222], [V2G2-519]	
requirement		
Config Id	CF01	
PICS Selection	PICS_AC and PICS_MR and PICS_PnC	
	Initial conditions	
with {		
the IUT havi	ing sent Metering Receipt Request message	
}		
	Expected behaviour	
ensure that {		
when {		
ťŀ	he IUT receives the Metering Receipt Response message	
	containing AC_EVSEStatus	
	containing EVSENotification indicating 'StopCharging'	
}		
then {		
th	he IUT sends a Power Delivery Request message	
	containing a valid Header	
	containing a Body	
	containing Ready to charge State field indicating value 'FALSE'	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PWD/BV/04		
Test objective	Check that Power delivery Request message is sent after receiving		
	Metering Receipt Response message (scheduling renegotiation case)		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.2, 8.8.4.2.2		
Reference	[V2G2-221], [V2G2-222], [V2G2-522]		
requirement			
Config Id	CF01		
PICS Selection	PICS_AC and PICS_MR and PICS_PnC		
	Initial conditions		
with {			
the IUT hav	ring sent Metering Receipt Request message		
}			
	Expected behaviour		
ensure that {			
when {			
the IUT receives the Metering Receipt Response message			
	containing AC_EVSEStatus		
	containing EVSENotification indicating 'ReNegotiation'		
}			
then {			
	the ILIT conds a Dower Delivery Dequest message		
	the IUT sends a Power Delivery Request message containing a valid Header		
	containing a valid neader		
	containing a Body containing Ready to charge State field indicating value 'FALSE'		
	containing Ready to Charge State held indicating value TALSE containing ChargeProfile field indicating `renegotiation requested		
	values'		
	before V2G_EVCC_Sequence_Perfomance_Time expires		
	before \$25_2\$ co_bequence_1 enominates_11111e expires		
}			
1			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PWD/BV/05	
Test objective	Check that Power Delivery Request message is sent after receiving	
	Pre charge Response message	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.2, 8.8.4.2.3	
Reference	[V2G2-221], [V2G2-222], [V2G2-528]	
requirement		
Config Id	CF01	
PICS Selection	PICS_DC	
	Initial conditions	
with {		
the IUT hav	ring sent Pre charging Request message	
}		
	Expected behaviour	
ensure that {		
when {	•	
į t	the IUT receives the Pre charge Response message	
	containing ResponseCode field indicating value 'OK'	
}		
then {		
1	the IUT sends a Power Delivery Request message	
	containing a valid Header	
	containing a Body	
	containing Ready to charge State field indicating value 'TRUE'	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PWD/BV/06
Test objective	Check that Power Delivery Request message is sent after receiving
	Current Demand Response message (stop charging case)
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.2, 8.8.4.2.3
Reference	[V2G2-221], [V2G2-222], [V2G2-527]
requirement	
Config Id	CF01
PICS Selection	PICS_DC
	Initial conditions
with { the IUT have	ring sent Current Demand Request message
}	Expected behaviour
ensure that {	2/100000 20110110011
when {	
	the IUT receives the Current Demand Response message
	containing ResponseCode field indicating value 'OK'
}	
then {	
the IUT sends a Power Delivery Request message containing a valid Header containing a Body containing Ready to charge State field indicating value 'FALSE' before V2G_EVCC_Sequence_Perfomance_Time expires }	
}	

TP Id	TP/EVCC/ALM/PWD/BV/07	
Test objective	Check that the IUT stops session if a Power Delivery Response	
	message containing a 'FAILED' Response Code is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.3, 8.8.4.2.2	
Reference	[V2G2-515]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ing sent Power Delivery Request message	
}		
Expected behaviour		
ensure that {		
when {		
the IUT receives a Power Delivery Response message		
containing Response Code field indicating value 'ALM_FAIL'.		
then {		
the IUT stops the V2G Communication Session		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PWD/BV/08	
Test objective	Check that the IUT stops session if a Power Delivery Response	
	message containing a 'FAILED_ChargingProfileInvalid' Response Code	
	is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.3, 8.8.4.2.2	
Reference	[V2G2-515]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ring sent Power Delivery Request message	
}		
Expected behaviour		
ensure that {		
when {		
the IUT rec	eives a Power Delivery Response message	
	ining Response Code field indicating value	
`FAILED_ChargingProfileInvalid'.		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

TP Id	TP/EVCC/ALM/PWD/BV/09		
Test objective	Check that the IUT stops session if a Power Delivery Response message containing a 'FAILED_TariffSelectionInvalid' Response Code		
	is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.3, 8.8.4.2.2		
Reference	[V2G2-515]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Power Delivery Request message		
}			
Expected behaviour			
ensure that {			
when {	when {		
the IUT receives a Power Delivery Response message			
containing Response Code field indicating value			
`FAILED_TariffSelectionInvalid'.			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PWD/BV/10		
Test objective	Check that the IUT stops session if a Power Delivery Response		
	message containing a 'FAILED_PowerDeliveryNotApplied' Response		
	Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.9.3, 8.8.4.2.2		
Reference	[V2G2-515]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Power Delivery Request message		
}			
	Expected behaviour		
ensure that {			
when {	when {		
	the IUT receives a Power Delivery Response message		
conta	containing Response Code field indicating value		
`FAILED_PowerDeliveryNotApplied'.			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

B.2.12 Session Stop

```
TP Id
                   TP/EVCC/ALM/SST/BV/01
  Test objective
                   Check that Session Stop Request message is sent after receiving
                   Power Delivery Response message
                   ISO/IEC 15118-DIS-2, Section 8.4.1.12.2, 8.8.4.2.2, 8.8.4.2.3
   Reference
                   [V2G2-239], [V2G2-520], [V2G2-619]
   Reference
  requirement
    Config Id
                   CF01
 PICS Selection
                                   Initial conditions
with {
       the IUT having sent Power Delivery Request message
               containing ReadyToChargeState field indicating value 'FALSE'
                                 Expected behaviour
ensure that {
            when {
                 the IUT receives the Power Delivery Response message
                    containing Response Code field indicating value 'OK'
           then {
                 the IUT sends a Session Stop Request message
                    containing a valid Header
                     containing a Body
                     before V2G_EVCC_Sequence_Perfomance_Time expires
           }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/SST/BV/02
Test objective	Check that Session Stop Request message is sent after receiving
	Welding Detection Response message
Reference	ISO/IEC 15118-DIS-2, Section 8.4.1.12.2, 8.8.4.2.3
Reference	[V2G2-239], [V2G2-535]
requirement	
Config Id	CF01
PICS Selection	PICS DC
	Initial conditions
with {	
the IUT hav	ring sent Welding Detection Request message
	taining EVReady field indicating value 'FALSE'
}	3,
	Expected behaviour
ensure that {	•
when {	
	the IUT receives the Welding Detection Response message
	containing Response Code field indicating value 'OK'
}	
then {	
the IUT sends a Session Stop Request message	
	containing a valid Header
	containing a Body
	before V2G_EVCC_Sequence_Perfomance_Time expires
3	before \$20_E\$66_5equence_i chomanice_time expires
J	

TP Id	TP/EVCC/ALM/SST/BV/03		
Test objective	Check that the IUT closes session if a Session Stop Response		
	message containing a 'FAILED' Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.1		
Reference	[V2G2-507]		
requirement			
Config Id	CF01		
PICS Selection			
	Initial conditions		
with {			
the IUT hav	ing sent Session Stop Request message		
}			
	Expected behaviour		
ensure that {			
when {	when {		
	the IUT receives a Session Stop Response message		
containing Response Code field indicating value 'FAILED'.			
then {			
the IUT stops the V2G Communication Session			
_ }			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.13 Charging status

TP Id	TP/EVCC/ALM/CHS/BV/01		
Test objective	Check that Charging Status Request message is sent after receiving		
	Power Delivery Response message		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.2.2.2, 8.8.4.2.2		
Reference	[V2G2-242], [V2G2-514]		
requirement			
Config Id	CF01		
PICS Selection	PICS_CHS and PICS_AC		
	Initial conditions		
with {			
the IUT hav	ving sent Power Delivery Request message		
}			
	Expected behaviour		
ensure that {			
when {			
	the IUT receives the Power Delivery Response message		
	containing ResponseCode field indicating value 'OK'		
}			
then {			
	the IUT sends a Charging status Request message		
containing a valid Header			
	containing a Body		
1	before V2G_EVCC_Sequence_Perfomance_Time expires		
}			
_ }			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CHS/BV/02
Test objective	Check that Charging Status Request message is sent after receiving
	Charging Status Response message (charge loop)
Reference	ISO/IEC 15118-DIS-2, Section 8.4.2.2.1, 8.8.4.2.2
Reference	[V2G2-242], [V2G2-516]
requirement	
Config Id	CF01
PICS Selection	PICS_CHS and PICS_AC
	Initial conditions
with {	
the IUT hav	ring sent Charging Status Request message
}	
	Expected behaviour
ensure that {	
when -	
	the IUT receives the Charging Status Response message
	containing ResponseCode field indicating value 'OK'
	containing ReceiptRequired field indicating value 'FALSE'
}	
then {	
the IUT sends a Charging status Request message	
containing a valid Header	
	containing a Body
	before V2G_EVCC_Sequence_Perfomance_Time expires
}	
}	

TP Id	TP/EVCC/ALM/CHS/BV/03	
Test objective	Check that Charging Status Request message is sent after receiving	
	Metering Receipt Response message (charge continues)	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.2.2.1, 8.8.4.2.2	
Reference	[V2G2-242], [V2G2-518]	
requirement		
Config Id	CF01	
PICS Selection	PICS_CHS and PICS_MR and PICS_AC	
	Initial conditions	
with {		
the IUT hav	ring sent Metering Receipt Request message	
}		
	Expected behaviour	
ensure that {		
when -		
	the IUT receives the Metering Receipt Response message	
	containing ResponseCode field indicating value 'OK'	
}		
then {		
1	the IUT sends a Charging status Request message	
	containing a valid Header	
	containing a Body	
	before V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CHS/BV/04		
Test objective	Check that the IUT stops session if a Charging status Response		
	message containing a 'ALM_FAIL' Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.4.2.2.2		
Reference	[V2G2-511]		
requirement			
Config Id	CF01		
PICS Selection	PICS_CHS and PICS_AC		
	Initial conditions		
with {			
the IUT having sent Charging status Request message			
}			
Expected behaviour			
ensure that {	ensure that {		
when {			
the IUT receives a Charging status Response message			
conta	ining Response Code field indicating value 'FAILED'.		
then {			
the IUT stops the V2G Communication Session			
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.14 Metering Receipt

TP Id	TP/EVCC/ALM/MR/BV/01
Test objective	Check that Metering Receipt Request message is sent after receiving
	Charging status Response message
Reference	ISO/IEC 15118-DIS-2, Section 8.4.2.3.2, 8.8.4.2.2
Reference	[V2G2-245], [V2G2-246], [V2G2-512]
requirement	
Config Id	CF01
PICS Selection	PICS_MR and PICS_AC and PICS_PnC
	Initial conditions
with {	
the IUT hav	ring sent Charging status Request message
	Expected behaviour
ensure that {	
when {	
į t	the IUT receives the Charging Status Response message
	containing ResponseCode field indicating value 'OK'
	containing ReceiptRequired field indicating value 'TRUE'
}	
then {	des TUT and des Malacines Describt Describt Describt
	the IUT sends a Metering Receipt Request message
	containing a valid Header
	containing a Body
	containing SessionID containing Meterinfo
	containing MeterIIIo
	containing MeterID containing MeterReading
	containing Multiplier field
	containing Multiplier Held
	containing SigMeterReading
	containing Signeter Reading containing Meterstatus
	containing TMeter
	before V2G_EVCC_Sequence_Perfomance_Time expires
}	12::::: 12:2_1:00_004u0::00_: 0::0:::u00_:::::0 0::pii:00
}	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/MR/BV/02		
Test objective	Check that the IUT stops session if a Metering Receipt Response		
	message containing a 'FAILED_MeteringSignatureNotValid' Response		
	Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.2		
Reference	[V2G2-517]		
requirement			
Config Id	CF01		
PICS Selection	PICS_MR and PICS_AC and PICS_PnC		
	Initial conditions		
with {			
the IUT hav	ing sent Metering receipt Request message		
}			
	Expected behaviour		
ensure that {			
when {			
	the IUT receives a Metering Receipt Response message		
	ining Response Code field indicating value a		
`FAILED_MeteringSignatureNotValid'.			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			

TP Id	TP/EVCC/ALM/MR/BV/03		
Test objective	Check that the IUT stops session if a Metering Receipt Response		
	message containing a 'FAILED' Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.2		
Reference	[V2G2-517]		
requirement			
Config Id	CF01		
PICS Selection	PICS_MR and PICS_AC and PICS_PnC		
	Initial conditions		
with {			
the IUT hav	ing sent Metering Receipt Request message		
}			
	Expected behaviour		
ensure that {			
when {			
	the IUT receives a Metering Receipt Response message		
containing Response Code field indicating value 'FAILED'.			
then {			
the IUT stops the V2G Communication Session			
_ }			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.15 Cable Check

TP Id	TP/EVCC/ALM/CCK/BV/01
Test objective	Check that Cable Check Request message is sent after receiving
	Charge Parameter Discovery Response message
Reference	ISO/IEC 15118-DIS-2, Section 8.4.3.2.2, 8.8.4.2.3
Reference	[V2G2-249], [V2G2-250], [V2G2-599]
requirement	
Config Id	CF01
PICS Selection	PICS_DC
	Initial conditions
with {	
the IUT hav	ving sent Charge Parameter Discovery Request message
}	
	Expected behaviour
ensure that {	
when -	·
1	the IUT receives the Charge Parameter Discovery Response message
,	containing ResponseCode field indicating value 'OK'
} then (
then {	the IUT sends a Cable Check Request message
	containing a valid Header
	containing a Body
containing DC_EVStatus	
containing EVReady	
containing EVErrorCode	
	containing EVRESSSOC
	before V2G_EVCC_Sequence_Perfomance_Time expires
}	
}	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

```
TP/EVCC/ALM/CCK/BV/02
      TP Id
                    Check that Cable Check Request message is resent after receiving
  Test objective
                    Cable Check Response message (SECC needs extra time for request
                    ISO/IEC 15118-DIS-2, Section 8.4.3.2.2, 8.8.4.2.3
[V2G2-249], [V2G2-250], [V2G2-617]
    Reference
    Reference
   requirement
                    CF01
    Config Id
 PICS Selection
                    PICS_EVCC
                                     Initial conditions
with {
        the IUT having sent Cable Check Request message
                                   Expected behaviour
ensure that {
            when {
                   the IUT receives the Cable Check Response message
                      containing ResponseCode field indicating value 'OK'
                      containing EVSEProcessing field incating value 'Ongoing'
            \label{eq:then} \} then \{
                   the IUT resends a Cable Check Request message
                      containing a valid Header
                      containing a Body
                         containing DC_EVStatus
                            containing EVReady
                            containing EVErrorCode
                            containing EVRESSSOC
            before V2G_EVCC_Sequence_Perfomance_Time expires
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CCK/BV/03		
Test objective	Check that the IUT stops session if a Cable Check Response message		
	containing a 'FAILED' Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.3		
Reference	[V2G2-524]		
requirement			
Config Id	CF01		
PICS Selection	PICS_DC		
	Initial conditions		
with {			
the IUT hav	ing sent Cable Check Request message		
}	}		
	Expected behaviour		
ensure that {			
when {			
the IUT rec	eives a Cable Check Response message		
containing Response Code field indicating value 'FAILED'			
}			
then {			
the IUT stops the V2G Communication Session			
}			
}			
·			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.16 Pre Charge

TP Id	TP/EVCC/ALM/PCH/BV/01	
Test objective	Check that Pre Charge Request message is sent after receiving Cable	
	Check Response message	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.3.3.2, 8.8.4.2.3	
Reference	[V2G2-253], [V2G2-254], [V2G2-525]	
requirement		
Config Id	CF01	
PICS Selection	PICS_DC	
	Initial conditions	
with {		
the IUT hav	ing sent Cable Check Request message	
}		
	Expected behaviour	
ensure that {		
when {		
t	he IUT receives the Cable Check Response message	
	containing ResponseCode field indicating value 'OK'	
,	containing EVSEProcessing indicating value 'Finished'	
} then {		
	he IUT sends a Pre Charge Request message	
l	containing a valid Header	
	containing a Valid Header	
	containing DC_EVStatus	
	containing EVReady	
	containing EVErrorCode	
	containing EVRESSSOC	
containing EVNESSSOC containing EVTargetVoltage		
containing Multiplier field		
containing Value field		
containing EVTargetCurrent		
	containing Multiplier field	
	containing Value field	
before	V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PCH/BV/02	
Test objective	Check that Pre Charge Request message is sent after receiving Pre	
	Charge Response message	
Reference	ISO/IEC 15118-DIS-2, Section 8.4.3.3.2, 8.8.4.2.3	
Reference	[V2G2-253], [V2G2-254], [V2G2-618]	
requirement		
Config Id	CF01	
PICS Selection	PICS_DC	
	Initial conditions	
with {		
the IUT hav	ving sent Pre Charge Request message	
}		
	Expected behaviour	
ensure that {		
when -	{	
	the IUT receives the Pre Charge Response message	
	containing EVSEPresentVoltage indicating a value which does not	
fulfil the voltage th	reshold requirement of the EV.	
}		
then {		
	the IUT sends a Pre charge Request message	
	containing a valid Header	
	containing a Body	
	containing DC_EVStatus	
containing EVReady		
containing EVErrorCode		
containing EVRESSSOC		
containing EVTargetVoltage		
containing Multiplier field		
containing Value field		
containing EVTargetCurrent		
	containing Multiplier field	
	containing Value field	
before	V2G_EVCC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/PCH/BV/03	
Test objective	Check that the IUT stops session if a Pre Charge Response message	
	containing a 'FAILED' Response Code is received	
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.3	
Reference	[V2G2-526]	
requirement		
Config Id	CF01	
PICS Selection	PICS_DC	
	Initial conditions	
with {		
the IUT hav	ing sent Pre Charge Request message	
}		
	Expected behaviour	
ensure that {		
when {		
the IUT rec	eives a Pre Charge Response message	
containing Response Code field indicating value 'FAILED'		
}		
then {		
the IUT stops the V2G Communication Session		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
-		Contract N. 285285

B.2.17 Current Demand

TP Id	TP/EVCC/ALM/CD/BV/01
Test objective	Check that Current Demand Request message is sent after receiving
	Power Delivery Response message
Reference	ISO/IEC 15118-DIS-2, Section 8.4.3.4.2, 8.8.4.2.3
Reference	[V2G2-257], [V2G2-258], [V2G2-530]
requirement	
Config Id	CF01
PICS Selection	PICS_DC
	Initial conditions
with {	
the IUT hav	ring sent Power Delivery Request message
	Expected behaviour
ensure that {	
when {	
t	the IUT receives the Power Delivery Response message
	containing ResponseCode field indicating value 'OK'
}	
then {	
	the IUT sends a Current Demand Request message
	containing a valid Header
	containing a Body
	containing DC_EVStatus
	containing EVReady
	containing EVErrorCode containing EVRESSSOC
	containing EVRESSOC containing ChargingComplete
	containing ChargingComplete containing EVTargetCurrent
	containing Evrargetedirent
	containing Value field
containing Value Held	
	containing Multiplier field
	containing Value field
before	V2G_EVCC_Sequence_Perfomance_Time expires
}	
}	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CD/BV/02
Test objective	Check that Current Demand Request message is sent after receiving
	Current Demand Response message (metering loop) while
	continuing charging process
Reference	ISO/IEC 15118-DIS-2, Section 8.4.3.4.2, 8.8.4.2.3
Reference	[V2G2-257], [V2G2-258], [V2G2-531]
requirement	
Config Id	CF01
PICS Selection	PICS_DC
	Initial conditions
with {	
	ring sent Current Demand Request message
}	
	Expected behaviour
ensure that {	
when {	
t	the IUT receives the Current Demand Response message
	containing ResponseCode field indicating value 'OK'
}	
then {	
t	the IUT sends a Current Demand Request message
	containing a valid Header
	containing a Body
	containing DC_EVStatus
	containing EVReady
	containing EVErrorCode
	containing EVRESSSOC
	containing ChargingComplete
	indicating value 'FALSE'
	containing EVTargetCurrent
	containing Multiplier field
	containing Value field
	containing EVTargetVoltage
	containing Multiplier field
	containing Value field
before	V2G_EVCC_Sequence_Perfomance_Time expires
}	1
,	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/CD/BV/03
Test objective	Check that the IUT stops session if a Current Demand Response
	message containing a 'FAILED' Response Code is received
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.3
Reference	[V2G2-532]
requirement	
Config Id	CF01
PICS Selection	PICS_DC
	Initial conditions
with {	
the IUT hav	ing sent Current Demand Request message
}	
	Expected behaviour
ensure that {	·
when {	
the IUT rec	eives a Current Demand Response message
containing Response Code field indicating value 'FAILED'	
}	
then {	
the IUT stops the V2G Communication Session	
}	
}	
•	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

B.2.18 Welding Detection

```
TP Id
                   TP/EVCC/ALM/WD/BV/01
                   Check that Welding Detection Request message is sent after
  Test objective
                   receiving Power Delivery Response message (end of charge process)
   Reference
                   ISO/IEC 15118-DIS-2, Section 8.4.3.5.2, 8.8.4.2.3
    Reference
                   [V2G2-261], [V2G2-262], [V2G2-533]
  requirement
    Config Id
                   CF01
 PICS Selection
                   PICS DC
                                  Initial conditions
with {
       the IUT having sent Power Delivery Request message
           containing ReadyToChargeState field, indicating value 'FALSE'
                                 Expected behaviour
ensure that {
            when {
                 the IUT receives the Power Delivery Response message
                    containing ResponseCode field, indicating value 'OK'
           then {
                 the IUT sends a Welding Detection Request message
                    containing a valid Header
                    containing a Body
                      containing DC_EVStatus
                         containing EVReady
                         containing EVErrorCode
                         containing EVRESSSOC
            before V2G_EVCC_Sequence_Perfomance_Time expires
            }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/EVCC/ALM/WD/BV/02
Test objective	Check that Welding Detection Request message is sent after
	receiving Welding Detection Response message
Reference	ISO/IEC 15118-DIS-2, Section 8.4.3.5.2, 8.8.4.2.3
Reference	[V2G2-261], [V2G2-262], [V2G2-620]
requirement	
Config Id	CF01
PICS Selection	PICS_DC
	Initial conditions
with {	
the IUT hav	ring sent Welding Detection Request message
}	
	Expected behaviour
ensure that {	
when -	
į t	the IUT receives the Welding Detection Response message
}	
then {	
1	the IUT sends a Welding Detection Request message
	containing a valid Header
	containing a Body
	containing DC_EVStatus
	containing EVReady
	containing EVErrorCode
	containing EVRESSSOC
	V2G_EVCC_Sequence_Perfomance_Time expires
}	
}	

TP Id	TP/EVCC/ALM/WD/BV/03		
Test objective	Check that the IUT stops session if a Welding Detection Response		
	message containing a 'FAILED' Response Code is received		
Reference	ISO/IEC 15118-DIS-2, Section 8.8.4.2.3		
Reference	[V2G2-534]		
requirement			
Config Id	CF01		
PICS Selection	PICS_DC		
	Initial conditions		
with {			
the IUT hav	the IUT having sent Welding Detection Request message		
}			
	Expected behaviour		
ensure that {			
when {			
	eives a Welding Detection Response message		
conta	ining Response Code field indicating value 'FAILED'		
}			
then {			
the IUT stop	os the V2G Communication Session		
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

ANNEX C: TEST PURPOSES FOR SECC

C.1 SECC discovery

TP Id	TP/SECC/SDP/SRV/BV/01
Test objective	Check that the IUT replies to a SECC Discovery Request indicating
	SECC IP and Port
Reference	ISO/IEC 15118-2, 7.10.1.5
Reference	[V2G2-144], [V2G2-146], [V2G2-147], [V2G2-150], [V2G2-151], [V2G2-152],
requirement	[V2G2-153], [V2G2-154], [V2G2-155], [V2G2-156]
Config Id	CF02
PICS Selection	
	Initial conditions
with {	
the IUT ha	ving assigned an IP address
}	
	Expected behaviour
ensure that {	
when {	TUT was in a smill CECC Discours Dominat
	e IUT receives a valid SECC Discovery Request
} than (
then {	e IUT sends a valid SECC Discovery Response
}	to i schus a valiu sece discovery nespolise
3	
l J	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/SDP/SRV/BV/02	
Test objective	11/3LCC/3D1/3RV/DV/02	
lest objective	Check that the IUT replies to N consecutive SECC Discovery Request	
	indicating CECC ID and Dort	
	indicating SECC IP and Port	
Reference	ISO/IEC 15118-2, 7.10.1.5	
	[V2G2-146], [V2G2-147], [V2G 2-150], [V2G2-151], [V2G2-152], [V2G2-153],	
Reference		
requirement	[V2G2-154], V2G2-155], [V2G2-156]	
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the IUT having assigned an IP address		
}		
	Expected behaviour	
ensure that {	·	
when {		
1	IUT receives N consecutive valid SECC Discovery Request	
}	10 Freedres Westiscourie Fund 5200 Biscorery Request	
then {		
-	THE conds N unlid SECC Discovery Degranges	
_	IUT sends N valid SECC Discovery Responses	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/SDP/SRV/BV/03
Test objective	Check that if the IUT replies with TLS-security option to a SECC
	Discovery Request requesting TLS
Reference	ISO/IEC 15118-2, 7.10.1.8
Reference	[V2G2-624], [V2G2-626]
requirement	
Config Id	CF02
PICS Selection	PICS TLS
	Initial conditions
with {	
the IUT ha	ving assigned an IP address and
the IUT su	pporting TLS
}	
	Expected behaviour
ensure that {	
when {	
the	e IUT receives a valid SECC Discovery Request
	containing Security Encoding field indicating value "0x00"
	containing Transport Protocol field indicating value "0x00"
}	
then {	
the	e IUT sends a valid SECC Discovery Response
	containing Security Encoding field indicating value "0x00"
	containing Transport Protocol field indicating value "0x00"
}	
}	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/SDP/SRV/BV/04
Test objective	Check that if the IUT does not support TLS, it replies with no-
	security option to a SECC Discovery Request requesting TLS
Reference	ISO/IEC 15118-2, 7.10.1.8
Reference	[V2G2-624], [V2G2-627]
requirement	
Config Id	CF02
PICS Selection	
	Initial conditions
with {	
the IUT ha	ving assigned an IP address and
the IUT no	t supporting TLS
}	
	Expected behaviour
ensure that {	
when {	
the	E IUT receives a valid SECC Discovery Request
	containing Security Encoding field indicating value "0x00"
	containing Transport Protocol field indicating value "0x00"
}	
then {	
the	e IUT sends a valid SECC Discovery Response
	containing Security Encoding field indicating value "0x10"
	containing Transport Protocol field indicating value "0x00"
}	
}	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/SDP/SRV/BV/05
Test objective	
iese objective	Check that the IUT replies with no-security option to a SECC
	Discovery Request requesting no TLS
	Discovery Requesting no 125
Reference	ISO/IEC 15118-2, 7.10.1.8
Reference	,
requirement	
Config Id	CF02
PICS Selection	
	Initial conditions
with {	
the IUT hav	ving assigned an IP address and
the IUT not	supporting TLS
}	
	Expected behaviour
ensure that {	
when {	
the	IUT receives a valid SECC Discovery Request
	containing Security Encoding field indicating value "0x10"
	containing Transport Protocol field indicating value "0x00"
}	
then {	
the	IUT sends a valid SECC Discovery Response
	containing Security Encoding field indicating value "0x10"
	containing Transport Protocol field indicating value "0x00"
}	
_ }	

C.2 Application layer messages

C.2.1. Handshake Protocol

TP Id	TP/SECC/ALM/HP/BV/01	
Test objective	Check that SupportedApp Response message is sent after receiving	
	SupportedApp Request message	
Reference	ISO/IEC 15118-DIS-2, section 8.2.1, 8.2.2, 8.8.4.3	
Reference	[V2G2-168], [V2G2-169], [V2G2-176], [V2G2-178], [V2G2-541]	
requirement		
Config Id	CF01	
PICS Selection		
	Initial conditions	
with {	ing and CECC Discovery Response	
the IUT having sent SECC Discovery Response message		
}		
,	Expected behaviour	
ensure that {	·	
when -		
the IUT receives the SupportedApp Request message		
}		
then {	then {	
the IUT sends a SupportedApp Response message containing SchemaID		

```
containing ResponseCode field indicating value
'OK_SuccessfullNegotiation'
before V2G_EVCC_Sequence_Performance_Time expires
}
}
```

TP Id	TP/SECC/ALM/HP/BV/02
Test objective	Check that SupportedApp Response with minor version support
	message is sent after receiving SupportedApp Request message
Reference	ISO/IEC 15118-DIS-2, section 8.2.2
Reference	[V2G2-170]
requirement	
Config Id	CF01
PICS Selection	
	Initial conditions
with {	
the IUT hav	ving sent SECC Discovery Response message
}	
	Expected behaviour
ensure that {	
when {	
	the IUT receives the SupportedApp Request message
1	the major version number is not supported by IUT
4h a.a. C	}
then {	
1	the IUT sends a SupportedApp Response message
	containing a valid Header
	containing a Body
	containing SchemaID containing ResponseCode field indicating value 'OK_
	SuccessfulNegotiationWithMinorDeviation'
	before V2G_EVCC_Sequence_Performance_Time expires
}	before \$25_E\$66_5equence_i enormance_nine expires
}	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

```
TP Id
                   TP/SECC/ALM/HP/BV/03
                   Check that SupportedApp Response message failed is sent after
  Test objective
                   receiving SupportedApp Request message
                   ISO/IEC 15118-DIS-2, section 8.2.2
    Reference
                   [V2G2-172], [V2G2-549]
    Reference
  requirement
                   CF01
    Config Id
 PICS Selection
                                  Initial conditions
with {
       the IUT having sent SECC Discovery Response message
                                 Expected behaviour
ensure that {
            when {
                 the IUT receives the SupportedApp Request message
                 the major version number is not supported by IUT
                       }
           then {
                 the IUT sends a SupportedApp Response message
                    containing a valid Header
                    containing a Body
                       containing ResponseCode field indicating value 'Failed_
                      NoNegotiation'
                    before V2G_EVCC_Sequence_Performance_Time expires
           }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.2 Session Setup

TP Id	TP/SECC/ALM/SSE/BV/01	
Test objective	Check that Session Setup Response message is sent after receiving	
	Session Setup Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.2.3, 8.8.4.3.1	
Reference	[V2G2-184], [V2G2-190], [V2G2-191], [V2G2-543]	
requirement		
Config Id	CF02	
PICS Selection	PICS_SECC	
	Initial conditions	
with {		
the IUT hav	ring sent SupportedAppProtocol response message	
}		
	Expected behaviour	
ensure that {		
when {		
į t	the IUT receives the Session Setup Request message	
	containing SessionID '00'	
	}	
then {	I TUT I O I O I	
the IUT sends a Session Setup Response message		
	containing a valid Header	
containing a Body		
	containing ResponseCode field indicating value	
	'OK_NewSessionEstablished' containing EVSEID field	
	before V2G_SECC_Sequence_Perfomance_Time expires	
}	before v20_5LCC_5equefice_refloitiafice_fiffie expires	
] }		
J		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.3 Service Discovery

TP Id	TP/SECC/ALM/SDI/BV/01
Test objective	Check that Service discovery Response message is sent after
	receiving Service discovery Request message
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.3.3, 8.8.4.3.1
Reference	[V2G2-195], [V2G2-196], [V2G2-545]
requirement	
Config Id	CF02
PICS Selection	
	Initial conditions
with {	
the IUT hav	ring sent Session Setup response message
}	
	Expected behaviour
ensure that {	
when {	
t	the IUT receives the Service discovery Request message
	}
then {	
t	the IUT sends a Service Discovery Response message
	containing a valid Header
	containing a Body
	containing Response code indicating value 'OK'
	containing PaymentOption type field
	containing Charge Service
	containing service type
	containing Service Tag
	containing Service ID field
	containing Free Service field
	containing EnergyTransfer type field
Before \	/2G_SECC_Sequence_Perfomance_Time expires
}	
}	

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TD 7.1	TD/GEGG/ALM/GDT/DV/GG	
TP Id	TP/SECC/ALM/SDI/BV/02	
Test objective	Check that Service discovery Response message fail is sent after	
	receiving Service discovery Request message which is not processed	
	successfully	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.3.3, 8.8.4.3.1	
Reference	[V2G2-546]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ving sent Session Setup response message	
}		
	Expected behaviour	
ensure that {		
when {	[
the IUT receives the Service discovery Request message		
}		
then {		
_	the IUT sends a Service Discovery Response message	
containing a valid Header		
containing a Body		
containing Response code indicating value 'FAIL'		
	Before V2G_SECC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.4 Service Details

TP Id	TP/SECC/ALM/SDE/BV/01	
Test objective	Check that Service details Response message is sent after receiving	
	Service details Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.4.2, 8.8.4.3.1	
Reference	[V2G2-199], [V2G2-200], [V2G2-426], [V2G2-548]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ring sent Service Discovery response message	
}		
	Expected behaviour	
ensure that {		
when {		
į t	the IUT receives the Service details Request message	
	}	
then {		
į t	the IUT sends a Service Details Response message	
containing a valid Header		
containing a Body		
containing Response Code indicating value 'OK'		
containing ServiceID		
	containing ServiceParameterList	
_	V2G_SECC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/SDE/BV/02	
Test objective	Check that Service details Response message fail is sent after	
	receiving Service details Request message with invalid Service ID	
Reference	ISO/IEC 15118-DIS-2 Section 8.6.3.6, 8.8.3.1	
Reference	[V2G2-425], [V2G2-464]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
	ving sent Service Discovery response message	
}	, , ,	
	Expected behaviour	
ensure that {	-	
when {		
	the IUT receives the Service details Request message	
containing invalid service ID		
	}	
then {	,	
the IUT sends a Service Details Response message		
containing a valid Header		
containing a Body		
containing Response Code indicating value		
`FAILED_ServiceIDInvalid'		
Before \	V2G_SECC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.5 Service and Payment Selection

TP Id	TP/SECC/ALM/SPS/BV/01	
Test objective	Check that Service and Payment Selection Response message is sent	
	after receiving Service and Payment Selection Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.5.3, 8.8.4.3.1	
Reference	[V2G2-203], [V2G2-204], [V2G2-551]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ring sent Service Details response or service discovery response	
message		
}		
	Expected behaviour	
ensure that {		
when {		
t	the IUT receives the Service and Payment Selection Request message	
	}	
then {		
the IUT sends a Service and Payment Selection Response message		
containing a valid Header		
containing a Body		
	containing Response Code indicating value 'OK'	
	V2G_SECC_Sequence_Perfomance_Time expires	
}		
}		

TP Id	TP/SECC/ALM/SPS/BV/02
Test objective	Check that the IUT sends a Service and Payment selection Response message with Response Code 'FAILED_PaymentSelectionInvalid' if the SelectedPaymentOption (contained in the ServicePaymentSelectionReq message) is not part of the offered PaymentOptions of ServiceDiscoveryRes
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.5.3, 8.8.3.1
Reference requirement	[V2G2-465], [V2G2-466]

```
CF02
    Config Id
 PICS Selection
                                   Initial conditions
with {
   the IUT having sent Service Details response or service discovery response message
ensure that {
  when {
      the IUT receives the Service and Payment selection request message
        containing SelectedPaymentOption field
            indicating 'Selected PaymentOption not contained in the Service and
Payment selection message'
  then {
      the IUT sends a Service and Payment selection Response message
         containing a valid Header
         containing a Body
            containing Response Code field
             indicating value 'FAILED_PaymentSelectionInvalid"
   }
```

TP Id	TP/SECC/ALM/SPS/BV/03	
Test objective	Check that the IUT sends a Service and Payment selection Response	
	message with Response Code `FAILED_ServiceSelectionInvalid' if	
	Service and payment selection Request message contains an invalid	
	Service ID	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1	
Reference	[V2G2-467]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the IUT having sen	t Service Details response or service discovery response message }	
	<u> </u>	
ensure that {		
when {		
the IUT recei	ves the Service and Payment selection Request message	
containing	g SelectedServiceList	
containing a Service	eID which was not contained in the offered ServiceList of Service	
Discovery Response	e	
}		
then {		
the IUT sends a Service and Payment selection Response message		
containing a valid Header		
containing a Body		
containing Response Code field		
indicating value 'FAILED_ServiceSelectionInvalid'		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.6 Certificate Update

```
TP Id
                   TP/SECC/ALM/CU/BV/01
                   Check that Certificate update response message is sent after
  Test objective
                   receiving Certificate update Request message
    Reference
                   ISO/IEC 15118-DIS-2 Section 8.4.1.10.3, 8.8.4.3.1
                   [V2G2-231], [V2G2-232], [V2G2-557]
    Reference
  requirement
                   CF02
    Config Id
 PICS Selection
                   PICS_PnC and PICS_CU
                                  Initial conditions
with {
       the IUT having sent Service and Payment Selection response message
                                 Expected behaviour
ensure that {
            when {
                 the IUT receives the Certificate update Request message
                                }
           then {
                 the IUT sends a Certificate update Response message
                    containing a valid Header
                     containing a Body
                        containing Response code indicating value 'OK'
                        containing ContractSignatureCertChain
                        containing ContractSignaturePrivateKey
                        containing ContractEncryptionPrivateKey
                       containing ContractID
                        containing RetryCounter
                        containing DHParams
              }
           Before V2G_SECC_Sequence_Perfomance_Time expires
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CU/BV/02	
Test objective	Check that the IUT sends a Certificate Update Response message	
	with Response Code 'FAILED_CertChainError' if the	
	ContractSignatureCertChain contained in the Certificate Update	
	request message is not valid.	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1	
Reference	[V2G2-470]	
requirement		
Config Id	CF02	
PICS Selection	PICS_PnC and PICS_CU	
	Initial conditions	
with { IUT having sent Se	ervice and Payment Selection response message }	
ensure that {		
when {		
	ives the Certificate Update Request message	
containing	g an invalid ContractSignatureCertChain	
}		
then {		
	s a Certificate Update Response message	
	g a valid Header	
containing a Body		
containing Response Code field		
indicating value `FAILED_CertChainError'		
Performance Time expires		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CU/BV/03		
Test objective	Check that the IUT sends a Certificate Update Response message		
	with Response 'FAILED_NoCertificateAvailable' if the new certificate		
	can't be retrieved from secondary actor		
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1		
Reference	[V2G2-471]		
requirement			
Config Id	CF02		
PICS Selection	PICS_PnC and PICS_CU		
	Initial conditions		
with {			
IUT having sent Se	rvice and Payment Selection response message }		
ensure that {			
when {			
the IUT recei	ves the Certificate Update Request message		
}			
then {			
the IUT send	s a Certificate Update Response message		
containing	containing a valid Header		
containing a Body			
containing Response Code field			
indicating value 'FAILED_NoCertificateAvailable'			
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CU/BV/04		
Test objective			
	with Response Code 'FAILED_ContractCanceled' if the provided		
	ContractID in CertificateUpdateReq is not		
	accepted by secondary actor.		
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1		
Reference	[V2G2-472]		
requirement			
Config Id	CF02		
PICS Selection	PICS_PnC and PICS_CU		
	Initial conditions		
with {			
IUT having sent Se	rvice and Payment Selection response message }		
ensure that {			
when {	when {		
the IUT receives the Certificate Update Request message			
containing a ContractID not acceptable for a secondary actor			
}			
then {			
the IUT sends a Certificate Update Response message			
containing a valid Header			
containing a Body			
containing Response Code field			
	indicating value `FAILED_ContractCanceled'		
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CU/BV/05		
Test objective	Check that the IUT sends a Certificate Update Response message		
	with Response Code 'FAILED_CertificateExpired' if the contract		
	certificate contained in the CertificateUpdate Request message is not		
	valid.		
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1		
Reference	[V2G2-473]		
requirement			
Config Id	CF02		
PICS Selection	PICS_PnC and PICS_CU		
	Initial conditions		
with {			
IUT having sent Se	rvice and Payment Selection response message }		
ensure that {			
when {			
	the IUT receives the Certificate Update Request message		
containing an invalid contract certificate			
}			
then {			
the IUT sends a Certificate Update Response message			
containing a valid Header			
containing a Body			
	containing Response Code field		
	indicating value `FAILED_CertificateExpired'		
}	}		
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.7 Certificate Installation

```
TP/SECC/ALM/CI/BV/01
      TP Id
  Test objective
                   Check that Certificate Install response message is sent after
                   receiving Certificate Install Request message
    Reference
                   ISO/IEC 15118-DIS-2 Section 8.4.1.11.3, 8.8.4.3.1
    Reference
                   [V2G2-237], [V2G2-238], [V2G2-554]
  requirement
                   CF02
    Config Id
 PICS Selection
                    PICS_PnC and PICS_CI
                                   Initial conditions
with {
       the IUT having sent Service and Payment Selection response message
                                 Expected behaviour
ensure that {
            when {
                  the IUT receives the Certificate Install Request message
                                 }
            then {
                  the IUT sends a Certificate Install Response message
                     containing a valid Header
                     containing a Body
                        containing Response code indicating value 'OK'
                        containing ContractSignatureCertChain
                        containing ContractSignatureEncryptedPrivateKey
                        containing ContractID
                        containing DHParams
           Before V2G_SECC_Sequence_Perfomance_Time expires
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

	,		
TP Id	TP/SECC/ALM/CI/BV/02		
Test objective	Check that the IUT sends a Certificate Install Response message		
	with Response Code 'FAILED_CertificateExpired' if the		
	OEMProvisioningCert contained in the		
	CertificateInstallationReq message is not valid.		
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1		
Reference	[V2G2-468]		
requirement			
Config Id	CF02		
PICS Selection	PICS_PnC and PICS_CI		
	Initial conditions		
with {			
the IUT having sent	t Service and Payment Selection response message }		
ensure that {			
when {			
the IUT receives the Certificate Install Request message			
containing an invalid OEMProvisioningCert			
}			
then {	then {		
the IUT sends a Certificate Install Response message			
containing a valid Header			
containing a Body			
containing Response Code field			
	indicating value `FAILED_CertificateExpired'		
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CI/BV/03	
Test objective	Check that the IUT sends a Certificate Install Response message	
	with Response Code 'FAILED_NoCertificateAvailable' if the new	
	certificate cannot be retrieved from secondary actor	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1	
Reference	[V2G2-469]	
requirement		
Config Id	CF02	
PICS Selection	PICS_PnC and PICS_CI	
	Initial conditions	
with {		
the IUT having sent	t Service and Payment Selection response message }	
ensure that {		
when {		
the IUT receives the Certificate Install Request message		
}		
then {		
the IUT send	s a Certificate Install Response message	
containing	g a valid Header	
containing a Body		
containing Response Code field		
indicating value 'FAILED_NoCertificateAvailable'		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.8 Payment Details

TP Id	TP/SECC/ALM/PDT/BV/01	
Test objective	Check that Payment details Response message is sent after	
	receiving Payment details Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.6.3, 8.8.4.3.1	
Reference	[V2G2-208], [V2G2-209], [V2G2-560]	
requirement		
Config Id	CF02	
PICS Selection	PICS_PnC and PICS_PDT	
	Initial conditions	
with {		
the IUT hav	ring sent Service and Payment Selection Response message	
}		
	Expected behaviour	
ensure that {		
when {		
1	the IUT receives the Payment details Request message	
	}	
then {		
į t	the IUT sends a Payment details Response message	
containing a valid Header		
containing a Body		
containing Response Code indicating value 'OK'		
containing Genchallenge		
containing DateTimeNow		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/PDT/BV/02	
Test objective	Check that the IUT sends a Payment Details Response	
	message with Response Code 'FAILED_CertificateExpired' if the	
	contract certificate contained in the PaymentDetailsReq message in	
	attribute ContractSignatureCertChain is not valid.	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1	
Reference	[V2G2-474]	
requirement		
Config Id	CF02	
PICS Selection	PICS_PnC and PICS_PDT	
	Initial conditions	
with {		
the IUT hav	ving sent Service and Payment Selection Response message	
}		
ensure that {		
when {		
the IUT recei	ves the Payment Details request message	
containing	contract certificate in the PaymentDetails Request message in	
attribute ContractSignatureCertChain is not valid.		
}		
then {		
the IUT send	s a Payment Details selection Response message	
containing a valid Header		
containing a Body		
containing Response Code field		
indicating value `FAILED_CertificateExpired'		
}		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.9 Contract Authentication

TP Id	TP/SECC/ALM/CA/BV/01	
Test objective	Check that Contract Authentication Response message is sent after	
	receiving Contract Authentication Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.7.2, 8.8.4.3.1,	
Reference	[V2G2-212], [V2G2-213], [V2G2-563], [V2G2-687]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
	ring sent Service and Payment Selection response message or	
Payment Details re	sponse message	
}		
	Expected behaviour	
ensure that {		
when {	•	
the IUT receives the Contract Authentication Request message		
}		
then {		
the IUT sends a Contract Authentication Response message		
containing a valid Header		
containing a Body		
containing Response Code indicating value 'OK' containing EVSEProcessing indicating value 'Finished'		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		
}		
, J		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CA/BV/02	
Test objective	Check that the IUT sends a Contract Authentication Response	
	message with Response Code 'FAILED_ChallengeInvalid' if the	
	challenge response contained in the ContractAuthenticationReq	
	message in attribute GenChallenge is not valid versus the provided	
D (GenChallenge in PaymentDetailsRes	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1	
Reference	[V2G2-475]	
requirement		
Config Id	CF02	
PICS Selection	PICS_PnC and PICS_PDT	
	Initial conditions	
with {		
	sent a PaymentDetails response message	
containing a	valid GenChallenge	
ensure that {		
when {	in and the Combined And heartist in Decrease we are a	
	ives the ContractAuthentication Request message	
_	a GenChallenge different to the one sent in PaymentDetails response	
} then {		
•	a a Contract Authortication Decrease massage	
the IUT sends a ContractAuthentication Response message		
containing a valid Header containing a Body		
containing a Body containing Response Code field		
indicating value `FAILED_ChallengeInvalid'		
Before V2G_SECC_Sequence_Perfomance_Time expires }		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.10 Charge parameter Discovery

```
TP Id
                    TP/SECC/ALM/CPD/BV/01
                    Check that Charge Parameter Discovery response message is sent
  Test objective
                   after receiving Charge Parameter Discovery Request message
                   ISO/IEC 15118-DIS-2 Section 8.4.1.8.3, 8.8.4.3.2
    Reference
                   [V2G2-218], [V2G2-220], [V2G2-573]
    Reference
  requirement
                   CF02
    Config Id
 PICS Selection
                   PICS AC
                                   Initial conditions
with {
       the IUT having sent Contract Authentication response message
               containing EVSEProcessing indicating value 'Finished'
                                  Expected behaviour
ensure that {
            when {
                  the IUT receives the Charge Parameter Discovery Request message
            then {
                  the IUT sends a Charge Parameter Discovery Response message
                     containing a valid Header
                     containing a Body
                       containing Response Code indicating value 'OK'
                         containing AC_EVSECharge parameter
                           containing AC_EVSEStatus
                              indicating value 'ready to charge'
                           containing EVSEMaxVoltage
                              containing Multiplier field
                              containing Value field
                           containing EVSEMaxCurrent
                              containing Multiplier field
                              containing Value field
                           containing EVSEVoltage
                              containing Multiplier field
                              containing Value field
                        containing SAScheduleTupleList
                           containing SAScheduleTupleID
                           containing PMaxSchedule
                              containing PMaxScheduleID
                              containing PMaxScheduleEntry
                               containing Timeinterval
                               containing Relative Time interval
                               containing PMAX
                                    containing Multiplier field
                                    containing Value field
               }
           Before V2G_SECC_Sequence_Perfomance_Time expires
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id TP/SECC/ALM/CPD/BV/02 Test objective Check that Charge Parameter Discovery response message is sent after receiving Charge Parameter Discovery Request message Reference ISO/IEC 15118-DIS-2 Section 8.4.1.8.3, , 8.8.4.3.2 Reference requirement Config Id CF02 PICS Selection PICS DC Initial conditions with { the IUT having sent Contract Authentication response message containing EVSEProcessing indicating value 'Finished'} Expected behaviour ensure that { when { the IUT receives the Charge Parameter Discovery Request message			
Reference ISO/IEC 15118-DIS-2 Section 8.4.1.8.3, , 8.8.4.3.2 Reference Refe			
Reference Reference Reference Reference Reference Reference Reference Reference Requirement Config Id CF02 PICS Selection PICS DC Initial conditions With { the IUT having sent Contract Authentication response message containing EVSEProcessing indicating value 'Finished'} Expected behaviour ensure that { when { the IUT receives the Charge Parameter Discovery Request message containing a valid Header containing a valid Header containing a valid Header containing Besponse code indicating value 'OK' containing Response code indicating value 'OK' containing DC_EVSECharge parameter Containing DC_EVSECharge parameter containing DC_EVSEStatus containing DC_EVSEStatus containing EVSEPsoutification containing EVSEPsoutification containing EVSEMotification containing EVSEMotification containing Value field containing VSEMinvoltageLimit containing Value field containing SAScheduleTupleLISt containing Multiplier field containing SAScheduleTupleLID field containing SAScheduleTupleLID field containing PMaxScheduleEntry containing PMaxScheduleEntry containing Timeinterval	Test objective		
Reference requirement Config Id CF02 PICS Selection PICS_DC Initial conditions with { the IUT having sent Contract Authentication response message			
requirement Config Id CF02 PICS Selection PICS_DC Initial conditions with { the IUT having sent Contract Authentication response message containing EVSEProcessing indicating value 'Finished'} Expected behaviour ensure that {			
Config Id CF02 PICS Selection PICS DC Initial conditions with { the IUT having sent Contract Authentication response message		[V2G2-218], [V2G2-220], [V2G2-573]	
## PICS Selection PICS DC			
with { the IUT having sent Contract Authentication response message containing EVSEProcessing indicating value 'Finished')			
with {	PICS Selection		
the IUT having sent Contract Authentication response message containing EVSEProcessing indicating value 'Finished'} Expected behaviour ensure that { when { the IUT receives the Charge Parameter Discovery Request message } } then { the IUT sends a Charge Parameter Discovery Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEProcessing containing EVSEProcessing containing DC_EVSECharge parameter containing DC_EVSEStatus Code containing BVSEStatusCode containing BVSENotification containing EVSENotification containing EVSENotification containing EVSEMaxVoltageLimit containing EVSEMaxVoltageLimit containing BVSEMaxCurrentLimit containing BVSEMaxCurrentLimit containing EVSEMinVoltageLimit containing BVSEMinVoltageLimit containing BVSEMinVoltageLimit containing BVSEMinVoltageLimit containing BVSEMinVoltageLimit containing BVSEMinVoltageLimit containing BVSEMinVoltageLimit containing BVSEMinCurrentLimit BVSEMinCurrentLimit BVSEMinCurr		Initial conditions	
ensure that {			
ensure that {			
ensure that { when { the IUT receives the Charge Parameter Discovery Request message	conta		
when {		Expected behaviour	
the IUT receives the Charge Parameter Discovery Request message } then { the IUT sends a Charge Parameter Discovery Response message containing a valid Header containing a Response code indicating value 'OK' containing Response code indicating value 'OK' containing DC_EVSECharge parameter containing DC_EVSEStatus containing DC_EVSEStatus containing EVSEStatus containing NotificationMaxDelay containing EVSEMaxVoltageLimit containing Multiplier field containing Value field containing EVSEMaxCurrentLimit containing Multiplier field containing Value field containing Value field containing Value field containing Wultiplier field containing Wultiplier field containing Wultiplier field containing Wultiplier field containing Walue field containing Walue field containing Walue field containing Value field containing SAScheduleTupleList containing SAScheduleTupleList containing PMaxScheduleFilo containing PMaxScheduleFilo containing PMaxScheduleEntry containing Timeinterval		,	
then { the IUT sends a Charge Parameter Discovery Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEProcessing containing DC_EVSECharge parameter containing DC_EVSECharge parameter containing DC_EVSEStatus containing PSEStatusCode containing Revsessing containing EVSEMaxVoltageLimit containing EVSEMaxVoltageLimit containing EVSEMaxVoltageLimit containing Value field containing Value field containing Value field containing VSEMaxCurrentLimit containing Multiplier field containing EVSEMinVoltageLimit containing EVSEMinVoltageLimit containing EVSEMinVoltageLimit containing EVSEMinCurrentLimit containing SVSEMinCurrentLimit containing SVSEMinCurrentLimit containing Value field containing Value field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleLipt field containing PMaxSchedulefield containing PMaxSchedulefield containing PMaxScheduleEntry containing Timeinterval			
then { the IUT sends a Charge Parameter Discovery Response message containing a valid Header containing a body containing Response code indicating value 'OK' containing EVSEProcessing containing DC_EVSECharge parameter containing DC_EVSEStatus containing EVSEStatusCode containing EVSEStatusCode containing EVSENotification containing EVSEMaxVoltageLimit containing EVSEMaxVoltageLimit containing Multiplier field containing EVSEMaxCurrentLimit containing Multiplier field containing EVSEMaxCurrentLimit containing Selue field containing Multiplier field containing Value field containing Value field containing Value field containing Value field containing VSEMinCurrentLimit containing Wiltiplier field containing Value field containing Multiplier field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleList containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleID containing PMaxScheduleID containing Timeinterval	†		
the IUT sends a Charge Parameter Discovery Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEProcessing containing DC_EVSECharge parameter containing DC_EVSECtatus containing DC_EVSEStatus containing EVSEStatusCode containing EVSENotification MaxDelay containing EVSEMaxVoltageLimit containing Multiplier field containing WSEMaxCurrentLimit containing Walue field containing Walue field containing WISEMaxCurrentLimit containing Walue field containing VSEMinVoltageLimit containing Walue field containing VSEMinVoltageLimit containing Walue field containing EVSEMinCurrentLimit containing Multiplier field containing EVSEMinCurrentLimit containing Walue field containing Value field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedulefield containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing a body containing Response code indicating value 'OK' containing EVSEProcessing containing DC_EVSECharge parameter containing DC_EVSEStatus containing EVSEStatusCode containing EVSENotification containing EVSEMaxVoltageLimit containing Multiplier field containing Value field containing VSEMaxCurrentLimit containing Walue field containing VSEMinCurrentLimit containing Value field containing SAScheduleTupleList containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing PMaxScheduleEntry			
containing a Body containing Response code indicating value 'OK' containing EVSEProcessing containing DC_EVSECharge parameter containing DC_EVSEStatus containing EVSEStatusCode containing NotificationMaxDelay containing EVSEMaxVoltageLimit containing EVSEMaxVoltageLimit containing Multiplier field containing EVSEMaxCurrentLimit containing Multiplier field containing EVSEMinVoltageLimit containing Walue field containing EVSEMinVoltageLimit containing BVSEMinVoltageLimit containing Walue field containing VSEMinCurrentLimit containing Walue field containing Value field containing Walue field containing Walue field containing Walue field containing Value field containing Value field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing PMaxScheduleEntry	1		
containing Response code indicating value 'OK' containing EVSEProcessing containing DC_EVSECharge parameter containing DC_EVSEStatus containing EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEMaxVoltageLimit containing Multiplier field containing Value field containing Multiplier field containing Value field containing Value field containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing Value field containing Value field containing VSEMinCurrentLimit containing Multiplier field containing Value field containing Multiplier field containing Value field containing SVSEPeakCurrentRipple containing Value field containing SAScheduleTupleList containing SAScheduleTupleLibt containing PMaxScheduleID containing PMaxScheduleID containing PMaxScheduleID containing Tmeinterval			
containing EVSEProcessing containing DC_EVSECharge parameter containing DC_EVSEStatus containing EVSEStatusCode containing NotificationMaxDelay containing EVSEMaxVoltageLimit containing Multiplier field containing Value field containing Waltiplier field containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Walue field containing Value field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing SASCheduleTupleList containing SAScheduleTupleList containing PMaxScheduleID containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing DC_EVSECharge parameter containing DC_EVSEStatus containing EVSEStatusCode containing NotificationMaxDelay containing EVSEMaxVoltageLimit containing Multiplier field containing Walue field containing Walue field containing Walue field containing Wultiplier field containing EVSEMinCurrentLimit containing Multiplier field containing Walue field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing DC_EVSEStatus containing EVSEStatusCode containing NotificationMaxDelay containing EVSEMotification containing EVSEMaxVoltageLimit containing Multiplier field containing EVSEMaxCurrentLimit containing Multiplier field containing Value field containing Value field containing Woltiplier field containing Woltiplier field containing Multiplier field containing Multiplier field containing EVSEMinCurrentLimit containing EVSEMinCurrentLimit containing Multiplier field containing Walue field containing Woltiplier field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEMaxVoltageLimit containing Multiplier field containing Value field containing Wultiplier field containing Value field containing Value field containing EVSEMinVoltageLimit containing EVSEMinVoltageLimit containing Multiplier field containing Walue field containing EVSEMinCurrentLimit containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleLipt containing SAScheduleTupleLipt containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing NotificationMaxDelay containing EVSENotification containing EVSEMaxVoltageLimit containing Multiplier field containing EVSEMaxCurrentLimit containing Multiplier field containing Value field containing EVSEMinVoltageLimit containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing Value field containing Wiltiplier field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing EVSENotification containing EVSEMaxVoltageLimit containing Multiplier field containing Value field containing EVSEMaxCurrentLimit containing Multiplier field containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing PMaxScheduleEntry			
containing EVSEMaxVoltageLimit containing Multiplier field containing Value field containing EVSEMaxCurrentLimit containing Multiplier field containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing Value field containing Value field containing Multiplier field containing Value field containing Value field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing Multiplier field containing Value field containing EVSEMaxCurrentLimit containing Multiplier field containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing PMaxScheduleEntry			
containing Value field containing EVSEMaxCurrentLimit containing Multiplier field containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing EVSEMaxCurrentLimit containing Multiplier field containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing Value field containing Multiplier field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing Multiplier field containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing Value field containing Multiplier field containing Multiplier field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing Value field containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing Value field containing Multiplier field containing Multiplier field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing EVSEMinVoltageLimit containing Multiplier field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing EVSEPeakCurrentRipple containing Multiplier field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing Multiplier field containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing EVSEPeakCurrentRipple containing Multiplier field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing Value field containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing EVSEPeakCurrentRipple containing Multiplier field containing Value field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing EVSEMinCurrentLimit containing Multiplier field containing Value field containing EVSEPeakCurrentRipple containing Multiplier field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing Multiplier field containing Value field containing EVSEPeakCurrentRipple containing Multiplier field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing Value field containing EVSEPeakCurrentRipple containing Multiplier field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing EVSEPeakCurrentRipple containing Multiplier field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing Multiplier field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval	Containing value nea		
containing Multiplier field containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval	containing EVSEPeakCurrentRipple		
containing Value field containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval	• • • • • • • • • • • • • • • • • • • •		
containing SAScheduleTupleList containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval	containing Value field		
containing SAScheduleTupleID field containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing PMaxSchedule field containing PMaxScheduleID containing PMaxScheduleEntry containing Timeinterval			
containing PMaxScheduleEntry containing Timeinterval			
containing PMaxScheduleEntry containing Timeinterval	containing PMaxScheduleID		
	containing PMaxScheduleEntry		
containing Relative Time interval	containing Timeinterval		
containing PMAX			
containing Multiplier field			
containing Value field			
Before V2G_SECC_Sequence_Perfomance_Time expires			
}			
}	}		

TP Id	TD/CECC/ALM/CDD/DV/03	
	TP/SECC/ALM/CPD/BV/03	
Test objective	Check that the IUT sends a Charge Parameter Discovery Response	
	message with Response Code 'FAILED_WrongEnergyTransferType' if	
	the content of attribute 'EVRequestedEnergyTransferType' in the	
	ChargeParameterDiscoveryReq message is not valid, or does not fit	
	to the content of attribute EVChargeParameter.	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1,	
Reference	[V2G2-476]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ving sent Contract Authentication response message	
containing	g EVSEProcessing indicating value 'Finished'	
}	-	
}		
-		
ensure that {		
when {		
the IUT recei	ves the Charge Parameter Discovery Request message	
	/RequestedEnergyTransferType field	
indicating a value not contained in the Charge Parameter Discovery Response		
message'}		
then {		
the IUT sends a Charge Parameter Discovery Response message		
containing a valid Header		
containing a Valid Fleddel		
containing a Body containing Response Code field		
indicating value `FAILED_WrongEnergyTransferType'		
Before V2G SECC Sequence Performance Time expires		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

```
TP Id
                   TP/SECC/ALM/CPD/BV/04
                   Check that the IUT sends a Charge Parameter Discovery Response
  Test objective
                   message with Response Code 'FAILED WrongChargeParameter', if
                   the content of attribute 'EVChargeParameter' in the
                   ChargeParameterDiscoveryReq message is not valid
                   ISO/IEC 15118-DIS-2 Section 8.8.3.1, [V2G2-477]
    Reference
    Reference
  requirement
                   CF02
    Config Id
 PICS Selection
                                   Initial conditions
with {
       the IUT having sent Contract Authentication response message
         containing EVSEProcessing indicating value 'Finished'
}
ensure that {
   when {
      the IUT receives the Charge Parameter Discovery Request message
         containing EVChargeParameter field
             indicating a wrong parameter set, or one or multiple parameters that
cannot be interpreted
   then {
      the IUT sends a Charge Parameter Discovery Response message
         containing a valid Header
         containing a Body
            containing Response Code field
                  indicating value 'FAILED_WrongChargeParameter'.
            }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
-		Contract N. 285285

C.2.11 Power Delivery

TP Id	TP/SECC/ALM/PWD/BV/01	
Test objective	Check that Power delivery response message is sent after receiving	
	Power delivery Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.9.3, 8.8.4.3.2	
Reference	[V2G2-223], [V2G2-226], [V2G2-576]	
requirement		
Config Id	CF02	
PICS Selection	PICS_AC	
	Initial conditions	
with {		
the IUT hav	ring sent Charge Parameter Discovery response message	
}		
	Expected behaviour	
ensure that {		
when {		
1	the IUT receives the Power delivery Request message	
	containing ReadyToChargeState field set to 'TRUE'	
than (}	
then {	the ILIT conds a Dower delivery Despense message	
'	the IUT sends a Power delivery Response message	
containing a valid Header containing a Body		
containing a Body containing Response code indicating value 'OK'		
containing Response code indicating value OK containing AC_EVSEStatus		
containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE'		
containing RCD indicating value `FALSE'		
containing NotificationMaxDelay		
	containing EVSENotification	
}	J	
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

```
TP Id
                   TP/SECC/ALM/PWD/BV/01a
  Test objective
                   Check that Power delivery response message is sent after receiving
                   Power delivery Request message
                   ISO/IEC 15118-DIS-2 Section 8.4.1.9.3
    Reference
                   [V2G2-223], [V2G2-226], [V2G2-568]
    Reference
  requirement
                   CF02
    Config Id
 PICS Selection
                   PICS AC
                                   Initial conditions
with {
       the IUT having sent Charge Parameter Discovery response message
                                 Expected behaviour
ensure that {
            when {
                  the IUT receives the Power delivery Request message
                     containing ReadyToChargeState field set to 'FALSE'
            then {
                  the IUT sends a Power delivery Response message
                     containing a valid Header
                     containing a Body
                      containing Response code indicating value 'OK'
                      containing AC_EVSEStatus
                         containing PowerSwitch closed indicating value 'TRUE'
                         containing RCD indicating value 'FALSE'
                         containing NotificationMaxDelay
                         containing EVSENotification
               }
           Before V2G_SECC_Sequence_Perfomance_Time expires
```

```
TP Id
                   TP/SECC/ALM/PWD/BV/02
                   Check that Power delivery response message is sent after receiving
  Test objective
                   Power delivery Request message
                   ISO/IEC 15118-DIS-2 Section 8.4.1.9.3, 8.8.4.3.3
   Reference
                   [V2G2-223], [V2G2-226], [V2G2-590]
   Reference
  requirement
    Config Id
                   CF02
 PICS Selection
                   PICS_DC
                                  Initial conditions
with {
       the IUT having sent Pre charging response message
                                 Expected behaviour
ensure that {
           when {
                 the IUT receives the Power delivery Request message
                     containing ReadyToChargeState field set to 'TRUE'
              }
           then {
                 the IUT sends a Power delivery Response message
                    containing a valid Header
                     containing a Body
                        containing Response code indicating value 'OK'
                        containing DC_EVSEStatus
                             containing EVSEStatusCode
                             containing NotificationMaxDelay
                             containing EVSENotification
              }
           Before V2G_SECC_Sequence_Perfomance_Time expires
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/PWD/BV/02a	
Test objective	Check that Power delivery response message is sent after receiving	
	Power delivery Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.9.3, 8.8.4.3.3	
Reference	[V2G2-223], [V2G2-226], [V2G2-601]	
requirement		
Config Id	CF02	
PICS Selection	PICS_DC	
	Initial conditions	
with {		
the IUT hav	ving sent Pre charging response message	
}		
	Expected behaviour	
ensure that {		
when {		
t	the IUT receives the Power delivery Request message	
	containing ReadyToChargeState field set to 'FALSE'	
}		
then {		
	the IUT sends a Power delivery Response message	
	containing a valid Header	
	containing a Body	
	containing Response code indicating value 'OK'	
	containing DC_EVSEStatus	
containing EVSEStatusCode		
	containing NotificationMaxDelay	
,	containing EVSENotification	
}		
Refore \	V2G_SECC_Sequence_Perfomance_Time expires	
}	v20_5E00_50quence_renomance_mine expires	
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/PWD/BV/03	
Test objective	Check that the IUT sends a Power Delivery Response message with	
	Response 'FAILED_ChargingProfileInvalid', if the charging profile is	
	different from SAscheduleTuple (charging profile is an optional	
Reference	parameter in power delivery request) ISO/IEC 15118-DIS-2 Section 8.4.1.9.3, 8.8.3.1	
Reference	[V2G2-225], [V2G2-478]	
requirement	[VZGZ-ZZS], [VZGZ-476]	
Config Id	CF02	
PICS Selection	PICS AC	
FICS Selection	Initial conditions	
with {	Tilidal Colladions	
	t Charge Parameter Discovery response message }	
	, , , , , ,	
ensure that {		
when {		
	ves the Power Delivery Request message	
	containing 'ChargingProfile' field that violates a power limitation provided in	
	ter Discovery Response'	
}		
then {	a a Davier Delivery Dagrana grana	
the IUT sends a Power Delivery Response message		
containing a valid Header		
containing a Body containing Response Code field		
indicating value `FAILED_ChargingProfileInvalid'.		
Before V2G_SECC_Sequence_Performance_Time expires		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

```
TP/SECC/ALM/PWD/BV/04
      TP Id
                    Check that the IUT sends a Power Delivery Response message with
  Test objective
                    Response 'FAILED_TariffSelectionInvalid', if the selected tariff is
                    invalid
                   ISO/IEC 15118-DIS-2 Section 8.8.3.1 [V2G2-479]
    Reference
    Reference
  requirement
                   CF02
    Config Id
 PICS Selection
                   PICS_AC
                                   Initial conditions
with {
   the IUT having sent Charge Parameter Discovery response message
ensure that {
   when {
      the IUT receives the Power Delivery Request message
         containing 'ChargingProfile' field
             containing a SAtupleID which was not contained in the 'SASchedules'
attribute provided in 'Charge Parameter Discovery Response'.
  then {
      the IUT sends a Power Delivery Response message
         containing a valid Header
         containing a Body
            containing Response Code field
              indicating value 'FAILED_TariffSelectionInvalid'.
         Before V2G_SECC_Sequence_Perfomance_Time expires
            }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

```
TP Id
                   TP/SECC/ALM/PWD/BV/05
  Test objective
                   Check that the IUT sends a Power Delivery Response message with
                   Response 'FAILED_PowerDeliveryNotApplied' if the EVSE is not able
                   to deliver energy.
                   ISO/IEC 15118-DIS-2 Section 8.8.3.1
    Reference
                   [V2G2-480]
    Reference
  requirement
                   CF02
    Config Id
 PICS Selection
                   PICS_AC
                                  Initial conditions
with {
   the IUT having sent Charge Parameter Discovery response message and
   the IUT not being able to deliver energy
ensure that {
  when {
     the IUT receives the Power Delivery Request message
  then {
     the IUT sends a Power Delivery Response message
         containing a valid Header
         containing a Body
            containing Response Code field
             indicating value 'FAILED_PowerDeliveryNotApplied'.
        Before V2G_SECC_Sequence_Perfomance_Time expires
           }
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/PWD/BV/06	
Test objective	Check that the IUT sends a Power Delivery Response message with	
	Response 'FAIL' if the processing of the information is not successful.	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.4.3.3	
Reference	[V2G2-591]	
requirement		
Config Id	CF02	
PICS Selection	PICS_AC	
	Initial conditions	
with {		
the IUT having	sent Charge Parameter Discovery response message	
//TODO How to	simulate non successful information processing	
}		
ensure that {		
when {		
	ves the Power Delivery Request message	
}		
then {		
	s a Power Delivery Response message	
containing a valid Header		
containing a Body		
containing Response Code field		
indicating value `FAIL'.		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.12 Session Stop

TP Id	TP/SECC/ALM/SST/BV/01	
Test objective	Check that Session Stop response message is sent after receiving	
	Session Stop Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.12.3, 8.8.4.3.1	
Reference	[V2G2-240], [V2G2-241], [V2G2-571]	
requirement		
Config Id	CF02	
PICS Selection	PICS_AC	
	Initial conditions	
with {		
t	the IUT having received Power Delivery request message	
	containing ReadyToChargeStatus indicating value `FALSE' and	
the IUT having sen	t Power Delivery response message}	
	Expected behaviour	
ensure that {		
when {		
1	the IUT receives Session stop Request message	
	}	
then {		
	the IUT sends a Session stop Response message	
	containing a valid Header	
containing a Body		
	containing Response code indicating value 'OK'	
	V2G_SECC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/SST/BV/02		
Test objective			
rest objective	Session stop Request message		
Deference			
Reference	ISO/IEC 15118-DIS-2 Section 8.4.1.12.3		
Reference	[V2G2-572]		
requirement	0500		
Config Id	CF02		
PICS Selection			
	Initial conditions		
with {			
1	the IUT having received Power Delivery request message		
	containing ReadyToChargeStatus indicating value 'FALSE' and		
1	the IUT having sent Power Delivery response message		
}			
	Expected behaviour		
ensure that {			
when -			
+	the IUT receives Session stop Request message		
	}		
then {			
the IUT sends a Session stop Response message			
containing a valid Header			
containing a Body			
//TODO How to trigger FAIL response code from the IUT			
containing Response code indicating value `FAIL'			
Before V2G_SECC_Sequence_Perfomance_Time expires			
}			
1}			
L-4			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.13 Charging status

Test objective Check that Charging status response message is sent after receiving Charging status Request message Reference ISO/IEC 15118-DIS-2 Section 8.4.2.2.3, 8.8.4.3.2 Reference requirement Config Id CF02 PICS Selection Initial conditions with {	TP Id	TP/SECC/ALM/CHS/BV/01	
Reference ISO/IEC 15118-DIS-2 Section 8.4.2.2.3, 8.8.4.3.2 Reference requirement (V2G2-244], [V2G2-577] Config Id CF02 PICS Selection Initial conditions with { the IUT having sent Power delivery response message } Expected behaviour ensure that { when { the IUT receives the Charging status Request message } then IUT sends a Charging status Response message containing a valid Header containing Response code indicating value 'OK' containing Response code indicating value 'OK' containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing Notification MaxDelay containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires	Test objective Check that Charging status response message is sent after received		
Reference requirement Config Id CF02 PICS Selection Initial conditions with { the IUT having sent Power delivery response message } Expected behaviour ensure that { when { the IUT receives the Charging status Request message } then { the IUT sends a Charging status Response message	Charging status Request message		
requirement Config Id CF02 PICS Selection Initial conditions with { the IUT having sent Power delivery response message } Expected behaviour ensure that { when { the IUT receives the Charging status Request message } then { the IUT sends a Charging status Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing BVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires	Reference		
Config Id CF02 PICS Selection Initial conditions with {	Reference	[V2G2-243], [V2G2-244], [V2G2-577]	
### PICS Selection Initial conditions			
Initial conditions with {		CF02	
with {	PICS Selection		
the IUT having sent Power delivery response message Expected behaviour Ensure that { When { the IUT receives the Charging status Request message } then { the IUT sends a Charging status Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires		Initial conditions	
Expected behaviour ensure that { when { the IUT receives the Charging status Request message } then { the IUT sends a Charging status Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires	-		
ensure that { when { the IUT receives the Charging status Request message } then { the IUT sends a Charging status Response message containing a valid Header containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires	the IUT hav	ring sent Power delivery response message	
ensure that { when { the IUT receives the Charging status Request message } then { the IUT sends a Charging status Response message containing a valid Header containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires	}		
when {		Expected behaviour	
the IUT receives the Charging status Request message } then { the IUT sends a Charging status Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
then { the IUT sends a Charging status Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
then { the IUT sends a Charging status Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires	t		
the IUT sends a Charging status Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires		}	
containing a valid Header containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires		h. THT and a Chancing status Bases are	
containing a Body containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
containing Response code indicating value 'OK' containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
containing EVSEID containing AC_EVSEStatus containing PowerSwitch closed indicating value `TRUE' containing RCD indicating value `FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value `TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
containing AC_EVSEStatus			
containing PowerSwitch closed indicating value 'TRUE' containing RCD indicating value 'FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
containing RCD indicating value `FALSE' containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value `TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
containing NotificationMaxDelay containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
containing EVSENotification containing Receipt Required indicating value 'TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires			
containing Receipt Required indicating value `TRUE' Before V2G_SECC_Sequence_Perfomance_Time expires	· · · · · · · · · · · · · · · · · · ·		
Before V2G_SECC_Sequence_Perfomance_Time expires			
	Con	taning Necespe Nequired indicating value TNOL	
	Before \	/2G SECC Sequence Perfomance Time expires	
1 <i>7</i>)		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CHS/BV/02	
Test objective	Checks Charging status response message fail is sent after receiving	
	Charging status Request message if the processing of the information is	
	not successful	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.4.3.2	
Reference	[V2G2-578]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ving sent Power delivery response message	
}		
	Expected behaviour	
ensure that {		
when -		
1	the IUT receives the Charging status Request message	
	}	
then {		
the IUT sends a Charging status Response message		
containing a valid Header		
containing a Body		
containing Response code indicating value 'FAIL'		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.14 Metering Receipt

TP Id	TP/SECC/ALM/MR/BV/01	
Test objective	Checks Metering receipt response message is sent after receiving	
	Metering receipt Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.2.3.3, 8.8.4.3.2	
Reference	[V2G2-247], [V2G2-248], [V2G2-580]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the IUT hav	ring sent Charging status response message	
contain	ing ReceiptRequired field set to 'TRUE'	
}		
	Expected behaviour	
ensure that {		
when {		
t	the IUT receives Metering receipt Request message	
	}	
then {		
t	the IUT sends a Metering receipt Response message	
	containing a valid Header	
	containing a Body	
	containing Response code indicating value 'OK'	
containing AC_EVSEStatus		
containing PowerSwitch closed indicating value 'TRUE'		
containing RCD indicating value `FALSE'		
containing NotificationMaxDelay		
containing EVSENotification		
	Before V2G_SECC_Sequence_Perfomance_Time expires	
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TDIA	TD/CFCC/ALM/MD/DV/03	
TP Id	TP/SECC/ALM/MR/BV/02	
Test objective	Check that the IUT sends a Metering Receipt Response message	
	with Response Code 'FAILED_MeteringSignatureNotValid' if IUT is	
	not able to validate the signature, or the contained	
	meter	
	reading does not fit to the provided meter reading during	
	'ChargingStatusRes' and the IUT requires that the signature is	
	valid.	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.3.1	
Reference	[V2G2-481]	
requirement		
Config Id	CF02	
PICS Selection		
	Initial conditions	
with {		
the EVCC havin	g sent a Metering Receipt Request message	
}		
ensure that {		
when {		
the IUT rece	ives the Metering Receipt Request message	
}		
then {		
the IUT send	ls a Metering Receipt Response message	
	g a valid Header	
containing a Body		
containing Response Code field		
indicating value `FAILED_MeteringSignatureNotValid'		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}	}	
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.15 Cable Check

TP Id	TP/SECC/ALM/CCK/BV/01		
Test objective Check that Cable Check response message is sent after received			
Cable Check Request message			
Reference	ISO/IEC 15118-DIS-2 Section 8.4.3.2.3, 8.8.4.3.3		
Reference	[V2G2-251], [V2G2-252], [V2G2-584]		
requirement			
Config Id	CF02		
PICS Selection	PICS_DC		
	Initial conditions		
with {			
the IUT hav	ving sent Charge Parameter Discovery response message		
}			
	Expected behaviour		
ensure that {			
when -			
	the IUT receives the Cable Check Request message		
	}		
then {			
1	the IUT sends a Cable Check Response message		
	containing a valid Header		
	containing a Body		
	containing Response code indicating value 'OK'		
	containing DC_EVSEStatus		
	containing EVSEStatusCode		
containing NotificationMaxDelay			
containing EVSENotification			
containing EVSEProcessing indicating value 'Finished'			
}			
Before \	Before V2G_SECC_Sequence_Perfomance_Time expires		
}			
}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CCK/BV/02	
Test objective Check that Cable Check response message fail is sent after receiv		
	Cable Check Request message if the processing of the information is	
	not successful	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.4.3.3	
Reference	[V2G2-585]	
requirement		
Config Id	CF02	
PICS Selection	PICS_DC	
	Initial conditions	
with {		
the IUT hav	ving sent Charge Parameter Discovery response message	
}		
	Expected behaviour	
ensure that {		
when -	{	
the IUT receives the Cable Check Request message		
}		
then {		
the IUT sends a Cable Check Response message		
containing a valid Header		
containing a Body		
containing Response code indicating value `FAIL'		
}		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.16 Pre Charge

TP Id	TP/SECC/ALM/PCH/BV/01			
Test objective				
	Charge Request message			
Reference	ISO/IEC 15118-DIS-2 Section 8.4.3.3.3			
Reference	[V2G2-255], [V2G2-256], [V2G2-587]			
requirement				
Config Id	CF02			
PICS Selection	PICS_DC			
	Initial conditions			
with {				
the IUT hav	ving sent Cable Check response message			
}	5			
	Expected behaviour			
ensure that {				
when -				
	the IUT receives the Pre Charging Request message			
then {	}			
	the IUT sends a Pre Charging Response message			
'	containing a valid Header			
	containing a Body			
	containing Response code indicating value 'OK'			
	containing DC EVSEStatus			
	containing EVSEStatusCode			
	containing NotificationMaxDelay			
	containing EVSENotification			
	containing EVSEPresentVoltage			
	containing Multiplier field			
	containing Value field			
}				
Before \	V2G_SECC_Sequence_Perfomance_Time expires			
}				
}				

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/PCH/BV/02	
Test objective	Check that Pre Charge response message fail is sent after receiving	
	Pre Charge Request message if the processing of the information is	
	not successful	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.4.3.3	
Reference	[V2G2-588]	
requirement		
Config Id	CF02	
PICS Selection	PICS DC	
	Initial conditions	
with {		
_	ving sent Cable Check response message	
}		
	Expected behaviour	
ensure that {	•	
when -		
	the IUT receives the Pre Charging Request message	
}		
then {	,	
the IUT sends a Pre Charging Response message		
containing a valid Header		
containing a Body		
containing Response code indicating value 'FAIL'		
}		
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.17 Current Demand

Test objective Check that Current Demand response message is sent after receiving Current Demand Request message Reference ISO/IEC 15118-DIS-2 Section 8.4.3.4.3, 8.8.4.3.3 Reference requirement Config Id CF02 PICS Selection PICS_DC Initial conditions with { the IUT having sent Power delivery response message } Expected behaviour ensure that { when { the IUT sends a Current Demand Request message } the IUT sends a Current Demand Response message containing a valid Header containing a Body containing DC_EVSEStatus containing DC_EVSEStatus containing DC_EVSEStatus containing DC_EVSEStatus containing VSEPresent/Ottage containing VSEPresent/Ottage containing WItiplier field containing VSEPresentCurrent containing WItiplier field containing WItiplier field containing VSEPresentCurrent containing VSEPresentCurrent containing VSEPCUrrentLimitAchived containing EVSECurrentLimitAchived containing EVSEPowerLimitAchieved containing EVSEPowerLimitAchieved containing EVSEPowerLimitAchieved containing EVSEPOSEC_Sequence_Perfomance_Time expires } }	TP Id	TP/SECC/ALM/CD/BV/01		
Reference Reference Reference Reference Reference Reference Reference Reference Reference Requirement Reference Requirement Reference Requirement Reference	Test objective			
Reference requirement Config Id CF02 PICS Selection PICS DC Initial conditions With { the IUT having sent Power delivery response message } Expected behaviour ensure that { when { the IUT receives the Current Demand Request message } then { the IUT sends a Current Demand Response message containing a valid Header containing Body containing DC_EVSEStatus				
requirement Config Id CF02 PICS Selection PICS DC Initial conditions with { the IUT having sent Power delivery response message } Expected behaviour ensure that { when { the IUT receives the Current Demand Request message } then { the IUT sends a Current Demand Response message containing a valid Header containing a Body containing BC_EVSEStatus	Reference			
Config Id CF02 PICS Selection PICS_DC Initial conditions with { the IUT having sent Power delivery response message } Expected behaviour ensure that { when { the IUT receives the Current Demand Request message } then { the IUT sends a Current Demand Response message containing a valid Header containing a Body containing BC_EVSEStatus containing DC_EVSEStatus containing NotificationMaxDelay containing EVSENotification containing VSEPresentVoltage containing VSEPresentCurrent containing Value field containing VSIDEPresentCurrent containing Value field containing VSUECURRENT containing EVSECURRENT	Reference	[V2G2-259], [V2G2-260], [V2G2-593]		
PICS Selection PICS DC Initial conditions	requirement			
with {	Config Id	CF02		
with {	PICS Selection	PICS_DC		
the IUT having sent Power delivery response message Expected behaviour Expected behaviour		Initial conditions		
ensure that { when { the IUT receives the Current Demand Request message } then { the IUT sends a Current Demand Response message containing a valid Header containing a Body containing Besponse code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatus containing NotificationMaxDelay containing EVSEPresentVoltage containing Multiplier field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires	with {			
ensure that { when { the IUT receives the Current Demand Request message } then { the IUT sends a Current Demand Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing Value field containing VSEPresentCurrent containing Multiplier field containing Value field containing VSECurrentLimitAchived containing EVSECurrentLimitAchived containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires	the IUT hav	ving sent Power delivery response message		
ensure that { when { the IUT receives the Current Demand Request message } then { the IUT sends a Current Demand Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing Value field containing VSEPresentCurrent containing Multiplier field containing Value field containing VSECurrentLimitAchived containing EVSECurrentLimitAchived containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires	}	Eveneted helpovious		
when {	anauma black C	Expected benaviour		
the IUT receives the Current Demand Request message } then { the IUT sends a Current Demand Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing DC_EVSEStatus		r		
then { the IUT sends a Current Demand Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing Walltiplier field containing Multiplier field containing Walltiplier field containing Value field containing Value field containing EVSEPresentCurrent containing Systematical Containing Con				
then { the IUT sends a Current Demand Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing Wiltiplier field containing Multiplier field containing Wiltiplier field containing Wiltiplier field containing Value field containing Value field containing EVSEVurrentLimitAchived containing EVSEVoltageLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
the IUT sends a Current Demand Response message containing a valid Header containing a Body containing Response code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved provided the service of the servic	then 5			
containing a valid Header containing a Body containing Response code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing Value field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing a Body containing Response code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing Response code indicating value 'OK' containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing Value field containing VSECurrentLimitAchived containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing DC_EVSEStatus containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing Value field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing DC_EVSEStatusCode containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing Value field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires		containing recopolise code maleating value on		
containing NotificationMaxDelay containing EVSENotification containing EVSEPresentVoltage containing Multiplier field containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires		containing DC_EVSEStatus		
containing EVSENotification containing EVSEPresentVoltage		containing DC_EVSEStatusCode		
containing EVSENotification containing EVSEPresentVoltage		containing NotificationMaxDelay		
containing EVSEPresentVoltage		·		
containing Multiplier field containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing Value field containing EVSEPresentCurrent containing Multiplier field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing EVSEPresentCurrent				
containing Multiplier field containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing Value field containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing EVSECurrentLimitAchived containing EVSEVoltageLimitAchieved containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing EVSEVoltageLimitAchieved containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires				
containing EVSEPowerLimitAchieved } Before V2G_SECC_Sequence_Perfomance_Time expires	containing Evoleumentennitachived			
} Before V2G_SECC_Sequence_Perfomance_Time expires		containing EVSEVoltageLimitAchieved		
} Before V2G_SECC_Sequence_Perfomance_Time expires		containing EVSEDoward imitAchiavad		
Before V2G_SECC_Sequence_Perfomance_Time expires	٦	Containing EvserowerLimitAchieved		
	}			
	Refore	V2G_SECC_Sequence_Perfomance_Time_evnires		
, }		v20_5266_56quence_renomance_rime expires		
	}			

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

TP Id	TP/SECC/ALM/CD/BV/02	
Test objective	Check that Current Demand response message fail is sent after	
	receiving Current Demand Request message if the processing of the	
	information is not successful	
Reference	ISO/IEC 15118-DIS-2 Section 8.8.4.3.3	
Reference	[V2G2-595]	
requirement		
Config Id	CF02	
PICS Selection	PICS_DC	
	Initial conditions	
with {		
the IUT hav	ving sent Power delivery response message	
}		
	Expected behaviour	
ensure that {		
when {		
į	the IUT receives the Current Demand Request message	
	}	
then {		
the IUT sends a Current Demand Response message		
containing a valid Header		
containing a Body		
containing Response code indicating value 'FAIL'		
}		
Defens	VOC CECC Converse Perference Time aurilian	
Before V2G_SECC_Sequence_Perfomance_Time expires		
}		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

C.2.18 Welding Detection

TP Id	TP/SECC/ALM/WD/BV/01	
Test objective	Checkthat Welding Detection response message is sent after	
	receiving Welding Detection Request message	
Reference	ISO/IEC 15118-DIS-2 Section 8.4.3.5.3, 8.8.4.3.3	
Reference	[V2G2-263], [V2G2-264], [V2G2-597]	
requirement		
Config Id	CF02	
PICS Selection	PICS_DC	
	Initial conditions	
with {		
	ring received Power Delivery request message	
	ning ReadyToChargeParameter set to 'FALSE' and	
the IUT hav	ving sent Power delivery response message	
}		
	Expected behaviour	
ensure that {		
when {		
	the IUT receives the Welding Detection Request message	
} *han (
then {	the ILIT conds a Wolding Detection Despense massage	
	the IUT sends a Welding Detection Response message containing a valid Header	
	containing a Valid Header	
	containing a Body containing Response code indicating value 'OK'	
	containing Response code indicating value OK	
	containing DC_EVSEStatus	
	containing DC_EVSEStatusCode	
	containing NotificationMaxDelay	
	•	
containing EVSENotification		
containing EVSEPresentVoltage		
	containing Multiplier field	
,	containing Value field	
}		
Refore \	/2G_SECC_Sequence_Perfomance_Time expires	
}	20_5266_56quence_i enomunee_mine expires	
1		
J		

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

```
TP Id
                   TP/SECC/ALM/WD/BV/02
                   Checks Welding Detection response message fail is sent after
  Test objective
                   receiving Welding Detection Request message if the processing of the
                   information is not successful
                   ISO/IEC 15118-DIS-2 Section 8.8.4.3.3
    Reference
                   [V2G2-598]
    Reference
  requirement
                   CF02
    Config Id
 PICS Selection
                   PICS_DC
                                   Initial conditions
with {
       the IUT having received Power Delivery request message
            containing ReadyToChargeParameter set to 'FALSE' and
       the IUT having sent Power delivery response message
                                 Expected behaviour
ensure that {
            when {
                  the IUT receives the Welding Detection Request message
            then {
                  the IUT sends a Welding Detection Response message
                     containing a valid Header
                     containing a Body
                        containing Response code indicating value 'FAIL'
           Before V2G_SECC_Sequence_Perfomance_Time expires
```

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

ANNEX D: ATS CONVENTIONS

The following table shows the ETSI generic TTCN-3 naming conventions extracted from [4] which V2G ATS is based on:

Table 7. ETSI generic TTCN-3 naming conventions

Language element	Naming convention	Prefix	Example identifier
Module	Use upper-case initial letter	ItsV2G/ LibItsV2G	ItsV2G_TestCases
Group within a module	Use lower-case initial letter	none	messageGroup
Data type	Use upper-case initial letter	none	SetupContents
Message template	Use lower-case initial letter	m_	m_setupInit
Message template with wildcard or matching expression	Use lower-case initial letters	mw_	mw_anyUserReply
Port instance	Use lower-case initial letter	none	signallingPort
Test component instance	Use lower-case initial letter	none	userTerminal
Constant	Use lower-case initial letter	c_	c_maxRetransmission
Constant (defined within component type)	Use lower-case initial letter	cc_	cc_minDuration
External constant	Use lower-case initial letter	cx_	cx_macId
Function	Use lower-case initial letter	f_	f_authentication()
External function	Use lower-case initial letter	xf_	xf_calculateLength()
Altstep (incl. Default)	Use lower-case initial letter	a_	a_receiveSetup()
Test case	Use ETSI numbering	TC_	TC_COR_0009_47_ND
Variable (local)	Use lower-case initial letter	V_	v_macId
Variable (defined within a component type)	Use lower-case initial letters	vc_	vc_systemName
Timer (local)	Use lower-case initial letter	t_	t_wait
Timer (defined within a component)	Use lower-case initial letters	tc_	tc_authMin
Module parameters for other parameters	Use all upper case letters	PXT_	PXT_MAC_ID
Formal Parameters	Use lower-case initial letter	p_	p_macId
			Page 166 of 172

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

Enumerated Values	Use lower-case	е	e syncOk
	initial letter	_	

Besides these naming conventions, other recommendations are proposed with regarding to:

- Structure of data:
 - Types should be defined in alphabetic order within TTCN-3 groups within the same TTCN-3 module
 - All message types referenced in port type definitions and related to same interface should be defined in the same TTCN-3 group and in the same module
- Log Statement:
 - o All TTCN-3 log statements must follow the following format
 - Three asterisk should be used to precede the log text,
 - then the TTCN-3 testcase/function identifier in which the log statement is defined should follow,
 - then one of the categories INFO, WARNING, ERROR, PASS, FAIL, INCONC, TIMEOUT should follow,
 - then free text should follow,
 - and finally the log text should end with three asterisk


•

EXAMPLE: log("*** f_sendMsg: INFO: Message has been sent ***")


- o Any invocation of an external function must be followed by log statement
- Each TTCN-3 setverdict statement that sets a test component verdict to INCONC or FAIL should be preceded by a log statement or log statement feature as first defined in TTCN-3 version 3.4.1 should be used, where the comment is part of the setverdict statement

ANNEX E: V2G PROTOCOL EXCHANGE

E.1 Overview of AC V2G protocol message exchange



E.2 Overview of DC V2G protocol message exchange



PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

ANNEX F: WHAT IS TTCN-3?

The Testing and Test Control Notation Version 3 (TTCN-3) is a standardized testing technology developed and maintained by the European Telecommunication Standards Institute (ETSI) and specifically designed for testing and certification. The ETSI TTCN-3 standards have also been adopted by the International Telecommunication Union (ITU-T) in the Z.160 series.

TTCN-3 is a test specification language that applies to a variety of application domains and types of testing. It has been used since 2000 in standardization as well as in industry, research, international projects and academia. In response to the demands of the user community TTCN-3 is being continuously improved and extended.

TTCN-3 provides all the constructs and features necessary for black box testing. It embodies a rich typing system and powerful matching mechanisms, support for both message-based and procedure-based communication, timer handling, dynamic test configuration including concurrent test behavior, the concept of verdicts and verdict resolution and much more.

As a result of its intrinsic extensibility, TTCN-3 is able to import external data and type specifications directly and external implementations can be integrated in order to extend the functionality specified in the TTCN-3 standards. Several mappings of external data and type specifications such as ASN.1, IDL and XML are already standardized. Others can easily be added.

A TTCN-3 documentation notation based on embedded tags is also standardized in ES 201 873-10.

The abstract definition of test cases which is fundamental to TTCN-3 makes it possible to specify a non-proprietary test system which is independent of both platform and operating system. The abstract definitions can be either compiled or interpreted for execution.

The TTCN-3 reference architecture defines standardized interfaces for test control for encoding and decoding of data and for test execution.

F.1 TTCN-3 is easy to learn

The standardized testing language has the look and feel of a regular programming language but without the complexity that such languages often introduce as it concentrates exclusively on testing.

There are many tutorial and courses to learn TTCN-3, as well as a certification program. The standard itself provides examples that demonstrate the usage of the specific features of the language.

	Page 170 of 172
--	-----------------

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

The aim of TTCN-3 is to provide a well-defined syntax for the definition of tests independent of any application domain. The abstract nature of a TTCN-3 test system makes it possible to adapt a test system to any test environment. This separation significantly reduces the effort required for maintenance allows experts to concentrate on what to test and not on how.

The TTCN-3 language comprises:

- A well-defined static and operational semantics
- A rich type system
- A powerful built-in matching mechanism and matching expressions
- Snapshot semantics that ensure and preserve the order of external event arrival
- The ability to define tests with multiple test components
- Support for message-based as well as procedure-based communication paradigms
- Support for dynamic test configurations with test components that can be (re)created and (re)connected on-the-fly
- The ability to specify execution parameters at runtime to ease re-targeting of test suite execution in different testing environments
- Support for timers
- The ability to automate test execution driven by external sources using the TTCN-3 Test Management interface (TCI-TM)

F.2 TTCN-3 is internationally standardized

TTCN-3 was created by leading experts from industry and academia at the European Telecommunications Standards Institute (ETSI).

The standards address not only the language for specifying tests but also the interfaces that control and adapt a test to any given environment. The standardization of TTCN-3 means that users are not forced to rely on the use of one proprietary tool.

F.3 The TTCN-3 approach to testing is extremely flexible

- The language is completely independent of technology, operating system and implementation domain
- There are no practical limits to the extent that tests or test systems can be adapted to users' needs
 - Test systems can be integrated easily with the most appropriate test execution management software using TCI Test Management interface (TCI-TM)
 - Test execution traces can be visualized in any suitable format using the TCI Test Logging interface (TCI-TL)
 - Any encoding scheme can be implemented and integrated using the TCI Codec and value APIs
 - Test systems can be adapted to any communication mechanism using the TTCN-3 Runtime Interface (TRI) System Adapter

PowerUp Final V2G Architecture	Public	Copyright PowerUp
		Contract N. 285285

- Test systems can be adapted to any timing model using the TTCN-3 Runtime Interface (TRI) Platform Adapter
- It is scalable
 - Adaptations can be configured to the current needs while the test scripts remain unchanged and can be used in different development phases
 - Test components can be added to existing test cases to test new interfaces of the SUT
- Test components can be used both to test and to emulate interfaces
- Extensible
 - $\circ\quad$ Standardized mappings to other external type systems available such as ASN.1 and XML
 - Integration of external functionality is possible using the TRI Platform Adapter
 - o Multiple presentation formats are available textual and graphical

F.4 TTCN-3 can be used in many types of testing

It can be used for:

- Valid, invalid and inopportune testing
- Software module, unit, layer, protocol, integration and laboratory testing,
- Functional, load, distributed and testing
- · Regression, certification and approval testing

More details on TTCN-3 at www.ttcn-3.org.